

# MARCO POLO - 101 W 33RD STREET

SHEET INDEX			
SHEET NUMBER	SHEET NAME	SHEET FILE	LAST ISSUE DATE
A000	COVER	101_W_33rd_St_Shell.rvt	xxx
A001	CODE & LIFE SAFETY	101_W_33rd_St_Shell.rvt	xxx
A101	FLOOR PLAN - 1ST	101_W_33rd_St_Units.rvt	xxx
A102	FLOOR PLAN - 2ND	101_W_33rd_St_Units.rvt	xxx
A103	FLOOR PLAN - 3RD	101_W_33rd_St_Units.rvt	xxx
A104	FLOOR PLAN - ROOF	101_W_33rd_St_Shell.rvt	xxx
A150	REFLECTED CEILING PLANS	101_W_33rd_St_Units.rvt	xxx
A200	BUILDING ELEVATION - NORTH/WEST	101_W_33rd_St_Shell.rvt	xxx
A201	BUILDING ELEVATION - SOUTH/EAST	101_W_33rd_St_Shell.rvt	xxx
A300	BUILDING SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A301	BUILDING SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A302	BUILDING SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A303	BUILDING SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A400	WALL SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A401	WALL SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A402	WALL SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A410	STAIR SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A411	STAIR SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A412	STAIR SECTIONS	101_W_33rd_St_Shell.rvt	xxx
A470	UNIT PLANS - STUDIOS - LONG AND SHORT - (TYPE B ADA UNIT - 1ST FLOOR ONLY)	101_W_33rd_St_Units.rvt	xxx
A471	UNIT PLANS - (TYPE A ADA UNIT - 1ST FLOOR ONLY)	101_W_33rd_St_Units.rvt	xxx
A472	UNIT PLANS - 1BD - END UNITS	101_W_33rd_St_Units.rvt	xxx
A500	LARGE SCALE DETAILS	101_W_33rd_St_Details_C.rvt	xxx
A501	LARGE SCALE DETAILS	101_W_33rd_St_Details_C.rvt	xxx
A502	LARGE SCALE DETAILS	101_W_33rd_St_Details_C.rvt	xxx
A503	LARGE SCALE DETAILS	101_W_33rd_St_Details.rvt	xxx
A504	LARGE SCALE DETAILS	101_W_33rd_St_Details.rvt	xxx
A505	LARGE SCALE DETAILS	101_W_33rd_St_Details_C.rvt	xxx
A600	SCHEDULES	101_W_33rd_St_Units.rvt	xxx
A751	ADA SECTIONS/ELEVATIONS	101_W_33rd_St_Units.rvt	xxx
A800	PARTITION DETAILS - WOOD STUDS	101_W_33rd_St_Units.rvt	xxx
S0.0	TYPICAL GENERAL NOTES		xxx
S0.01	STATEMENT OF SPECIAL INSPECTIONS		xxx
S0.1	FOUNDATION PLAN	101_W_33rd_St_Structure.rvt	xxx
S1.1A	FOUNDATION NOTES AND 3D	101_W_33rd_St_Structure.rvt	xxx
S0.2	FRAMING PLAN - 2ND FLOOR	101_W_33rd_St_Structure.rvt	xxx
S0.3	FRAMING PLAN - 3RD FLOOR	101_W_33rd_St_Structure.rvt	xxx
S0.4	FRAMING PLAN - ROOF	101_W_33rd_St_Structure.rvt	xxx
S1.0	FOUNDATION DETAILS		xxx
S1.1	FOUNDATION DETAILS		xxx
S1.2	FOUNDATION DETAILS		xxx
S2.0	TYPICAL WOOD FRAMING DETAILS		xxx
S2.1	TYPICAL WOOD FRAMING WALL DETAILS		xxx
S2.2	TYPICAL WOOD FLOOR TRUSS DETAILS		xxx
S2.3	TYPICAL WOOD FRAMING LATERAL DETAILS		xxx
S2.4	TYPICAL WOOD ROOF TRUSS DETAILS		xxx
S2.5	TYPICAL STEEL DETAILS		xxx

CODE INFORMATION	
APPLICABLE CODES:	<p>GENERAL:</p> <ul style="list-style-type: none"> <li>BUILDING/DWELLING CODE IBC 2015 &amp; AHJ AMENDMENTS</li> </ul> <p>EXISTING:</p> <ul style="list-style-type: none"> <li>INTERNATIONAL EXISTING BUILDING CODE 2015 &amp; AHJ AMENDMENTS</li> </ul> <p>ENERGY CONSERVATION:</p> <ul style="list-style-type: none"> <li>INTERNATIONAL ENERGY CONSERVATION CODE 2015 &amp; AHJ AMENDMENTS</li> </ul> <p>PLUMBING:</p> <p>MECHANICAL:</p> <ul style="list-style-type: none"> <li>MECHANICAL CODE IMC 2015 &amp; AHJ AMENDMENTS</li> </ul> <p>ELECTRICAL:</p> <ul style="list-style-type: none"> <li>ELECTRICAL CODE NEC 2017 &amp; AHJ AMENDMENTS</li> </ul> <p>FIRE:</p> <ul style="list-style-type: none"> <li>FIRE/LIFE SAFETY CODE 2009 NFPA-1 &amp; AHJ AMENDMENTS</li> </ul> <p>ACCESSIBILITY:</p> <ul style="list-style-type: none"> <li>ANSI STANDARD A117.1-2009 - FOR ACCESSIBILITY</li> </ul> <p>FUEL:</p> <ul style="list-style-type: none"> <li>INTERNATIONAL FUEL GAS CODE 2015 &amp; AHJ AMENDMENTS</li> </ul>
CHAPTER 3 USE AND OCCUPANCY CLASSIFICATION:	310.4 RESIDENTIAL GROUP R-2
SECTION 420 GROUPS I-1, R-1, R-2, R-3 AND R-4	SECTION 420 GROUPS R-2 <ul style="list-style-type: none"> <li>FIRE PARTITIONS IN ACCORDANCE WITH SECTION 708</li> <li>HORIZONTAL ASSEMBLIES IN ACCORDANCE WITH SECTION 711.</li> </ul>
CHAPTER 5 CLASSIFICATION OF WORK:	NEW
504.3 HEIGHT IN FEET	R-2 - TYPE V (SPRINKLERED): <ul style="list-style-type: none"> <li>ACTUAL: 38FT</li> <li>ALLOWED: 40FT</li> </ul>
504.4 NUMBER OF STORIES	R-2 - TYPE V (SPRINKLERED): <ul style="list-style-type: none"> <li>ACTUAL: 3</li> <li>ALLOWED: 4</li> </ul>
504.2 ALLOWABLE AREA DETERMINATION & 504.3 FRONTAGE INCREASE:	<ul style="list-style-type: none"> <li>TABULAR PER FLOOR AREA LIMIT PER CHAPTER 5 = 7000 SQ.FT.</li> <li>ALLOW HEIGHT = 40 FT; ALLOW STORIES = 3</li> <li>GROUP R AND NFPA 13R? YES</li> <li>NFPA 13 SPRINKLERS? NO</li> <li>COMPUTE AREA INCREASE DUE TO FRONTAGE: FRONTAGE COEFFICIENT, IF 0.499</li> <li>PERIMETER: P 364 FT</li> <li>FRONTAGE PERIMETER, F 314 FT</li> <li>WEIGHTED AVERAGE DISTANCE FROM "F" = 24.24 FT</li> <li>COMPUTE ALLOWABLE PER STORY AREA, AA = AT + (NS X IF) = 10496.23 SQ.FT.</li> <li>MAXIMUM ALLOWABLE AREA = AA X 3 = 31488.68 SQ.FT.</li> <li>MAXIMUM NUMBER OF STORIES FOR GROUP R WITH NFPA 13R SPRINKLERS, PER SEC. 903.3.1.2 THIS CRITERIA IS MET, SO STORY LIMIT = 4</li> <li>THE REVISED ALLOWABLE HEIGHT IS 40 FT.</li> </ul>
508.3 NONSEPARATED OCCUPANCIES:	N/A
508.4 SEPARATED OCCUPANCIES	N/A
TABLE 401 FIRE-RESISTANCE RATING REQUIREMENTS FOR BUILDING ELEMENTS (HOURS)	<p>FOR TYPE VB</p> <p>STRUCTURAL FRAME: 0 HR</p> <p>BEARING WALLS- EXTERIOR: 0 HR</p> <p>BEARING WALLS- INTERIOR: 0 HR</p> <p>NON-BEARING WALLS- EXTERIOR - (SEE TABLE 602)</p> <p>NON-BEARING WALLS- INTERIOR: 0 HR</p> <p>FLOOR CONSTRUCTION: 0 HR</p> <p>ROOF CONSTRUCTION: 0 HR</p>
TABLE 402 FIRE-RESISTANCE RATING REQUIREMENTS FOR EXTERIOR WALLS BASED ON FIRE SEPARATION DISTANCE	<p>TYPE-VB</p> <p>FIRE SEPARATION DISTANCE</p> <ul style="list-style-type: none"> <li>X &lt; 5C = 1 HR</li> <li>5 ≤ X ≤ 10 = 1 HR</li> <li>10 &lt; X ≤ 30 = 0 HR</li> <li>X ≥ 30 = 0 HR</li> </ul>
708.3 FIRE-RESISTANCE RATING	CORRIDORS: 1/2HR RATED
711.2.4.3 DWELLING UNITS AND SLEEPING UNITS	BETWEEN DWELLING UNITS: 1HR RATED
SPRINKLERS (SECTION 903 AUTOMATIC SPRINKLER SYSTEMS):	NFPA13R SPRINKLER THROUGHOUT PROJECT (R-2)
SECTION 1020 CORRIDORS	CORRIDORS: 1/2HR RATED
SECTION 1004 OCCUPANT LOAD	SEE SECTION 1021 EGRESS BALCONIES FOR CORRIDOR RATING AT EXTERIOR WALL TABLE 1004.1.2 MAXIMUM FLOOR AREA ALLOWANCES PER OCCUPANT RESIDENTIAL: 200 GROSS
1006.2.1 EGRESS BASED ON OCCUPANT LOAD AND COMMON PATH OF EGRESS TRAVEL DISTANCE:	FOR R-2: MAXIMUM COMMON PATH WITH SPRINKLER SYSTEM: 125FT MAXIMUM OCCUPANT LOAD OF SPACE WITH ONE EXIT: 49 FOR R-2: 250 (W/SPRINKLER)
1020.4 DEAD ENDS:	50FT (WITH SPRINKLERS)
SECTION 1021 EGRESS BALCONIES	EXTERIOR EGRESS BALCONIES SHALL BE SEPARATED FROM THE INTERIOR OF THE BUILDING BY WALLS AND OPENING PROTECTIVES AS REQUIRED FOR CORRIDORS.  SECTION 1020 CORRIDORS 1020.1 CONSTRUCTION  CORRIDORS SHALL BE FIRE-RESISTANCE RATED IN ACCORDANCE WITH TABLE 1020.1. THE CORRIDOR WALLS REQUIRED TO BE FIRE-RESISTANCE-RATED SHALL COMPLY WITH SECTION 708 FOR FIRE PARTITIONS.  EXCEPTIONS: CORRIDORS ADJACENT TO THE EXTERIOR WALLS OF BUILDINGS SHALL BE PERMITTED TO HAVE UNPROTECTED OPENINGS ON UNRATED EXTERIOR WALLS WHERE UNRATED WALLS ARE PERMITTED BY TABLE 402 AND UNPROTECTED OPENINGS ARE PERMITTED BY TABLE 705.6
2902.1 MINIMUM NUMBER OF FIXTURES	CLASSIFICATION & OCCUPANCY: --- R-2 <ul style="list-style-type: none"> <li>WATER CLOSETS: 1 PER DWELLING</li> <li>LAVATORIES: 1 PER DWELLING</li> <li>BATHTUBS/ SHOWERS: 1 PER DWELLING</li> </ul>


PRELIMINARY - NOT FOR CONSTRUCTION




Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katherine@renovations.com | 979.450.9969



ARCHITECTURE  
Architect of Record: UKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@ukbarchitecture.com | 713.425.3076




Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720



MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com


This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set


OCCUPANT LOAD (BASED ON TABLE 1004.1.2)						
Level	Name	Occupancy	Area	Function of Space	Area Allowance Per Occupant	Occupant Load
3RD FLOOR	OUTDOOR CORRIDOR	R-2	635 SF	CIRCULATION	200	3.2
3RD FLOOR	STAIR	R-2	84 SF	CIRCULATION	200	0.4
3RD FLOOR	STAIR	R-2	81 SF	CIRCULATION	200	0.4
3RD FLOOR	BALCONY	R-2	123 SF	RESIDENTIAL	200	0.6
3RD FLOOR	BALCONY	R-2	123 SF	RESIDENTIAL	200	0.6
3RD FLOOR	PORCH	R-2	224 SF	RESIDENTIAL	200	1.1
3RD FLOOR	PORCH	R-2	107 SF	RESIDENTIAL	200	0.5
3RD FLOOR	PORCH	R-2	101 SF	RESIDENTIAL	200	0.5
3RD FLOOR	PORCH	R-2	142 SF	RESIDENTIAL	200	0.7
3RD FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
3RD FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
3RD FLOOR	STUDIO - T1	R-2	618 SF	RESIDENTIAL - ST	200	3.1
3RD FLOOR	STUDIO - T1	R-2	618 SF	RESIDENTIAL - ST	200	3.1
3RD FLOOR	STUDIO - T2	R-2	525 SF	RESIDENTIAL - ST	200	2.6
3RD FLOOR	STUDIO - T2	R-2	525 SF	RESIDENTIAL - ST	200	2.6
3RD FLOOR: 15			5447 SF			27.2
2ND FLOOR	OUTDOOR CORRIDOR	R-2	613 SF	CIRCULATION	200	3.1
2ND FLOOR	STAIR	R-2	84 SF	CIRCULATION	200	0.4
2ND FLOOR	STAIR	R-2	84 SF	CIRCULATION	200	0.4
2ND FLOOR	BALCONY	R-2	123 SF	RESIDENTIAL	200	0.6
2ND FLOOR	BALCONY	R-2	123 SF	RESIDENTIAL	200	0.6
2ND FLOOR	PORCH	R-2	334 SF	RESIDENTIAL	200	1.7
2ND FLOOR	PORCH	R-2	107 SF	RESIDENTIAL	200	0.5
2ND FLOOR	PORCH	R-2	101 SF	RESIDENTIAL	200	0.5
2ND FLOOR	PORCH	R-2	142 SF	RESIDENTIAL	200	0.7
2ND FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
2ND FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
2ND FLOOR	STUDIO - T1	R-2	617 SF	RESIDENTIAL - ST	200	3.1
2ND FLOOR	STUDIO - T1	R-2	617 SF	RESIDENTIAL - ST	200	3.1
2ND FLOOR	STUDIO - T2	R-2	525 SF	RESIDENTIAL - ST	200	2.6
2ND FLOOR	STUDIO - T2	R-2	525 SF	RESIDENTIAL - ST	200	2.6
2ND FLOOR: 15			5537 SF			27.7
1ST FLOOR	OUTDOOR CORRIDOR	R-2	759 SF	CIRCULATION	200	3.8
1ST FLOOR	STAIR	R-2	84 SF	CIRCULATION	200	0.4
1ST FLOOR	STAIR	R-2	84 SF	CIRCULATION	200	0.4
1ST FLOOR	PATIO	R-2	84 SF	RESIDENTIAL	200	0.4
1ST FLOOR	PATIO	R-2	149 SF	RESIDENTIAL	200	0.7
1ST FLOOR	PATIO	R-2	98 SF	RESIDENTIAL	200	0.5
1ST FLOOR	PATIO	R-2	96 SF	RESIDENTIAL	200	0.5
1ST FLOOR	PATIO	R-2	141 SF	RESIDENTIAL	200	0.8
1ST FLOOR	PATIO	R-2	90 SF	RESIDENTIAL	200	0.4
1ST FLOOR	PORCH	R-2	145 SF	RESIDENTIAL	200	0.7
1ST FLOOR	PORCH	R-2	97 SF	RESIDENTIAL	200	0.5
1ST FLOOR	PORCH	R-2	94 SF	RESIDENTIAL	200	0.5
1ST FLOOR	PORCH	R-2	86 SF	RESIDENTIAL	200	0.4
1ST FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
1ST FLOOR	1BD-T1	R-2	770 SF	RESIDENTIAL - 1BD	200	3.9
1ST FLOOR	STUDIO - T1	R-2	615 SF	RESIDENTIAL - ST	200	3.1
1ST FLOOR	STUDIO - T1	R-2	615 SF	RESIDENTIAL - ST	200	3.1
1ST FLOOR	STUDIO - T2	R-2	522 SF	RESIDENTIAL - ST	200	2.6
1ST FLOOR	STUDIO - T2	R-2	522 SF	RESIDENTIAL - ST	200	2.6
1ST FLOOR: 19			5842 SF			29.2
Grand total: 49			18262 SF			84.1




4B A001 LIFE SAFETY - 1ST FLOOR  
1/16" = 1'-0"




5 A001 LIFE SAFETY - ROOF  
1/16" = 1'-0"




6C A001 LIFE SAFETY - 2ND FLOOR  
1/16" = 1'-0"



1 A001 LIFE SAFETY SECTION - EAST/WEST  
1/16" = 1'-0"



4A A001 LIFE SAFETY - 3RD FLOOR  
1/16" = 1'-0"



EGRESS DATA	
EXIT ROUTE	DISTANCE
ROUTE 1	141' - 4"

RENOVATION Wranglers  
Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katherine@wranglers.com | 979.450.9969


ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

opening design  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set



FLOOR PLAN - 1ST FLOOR  
1/4" = 1'-0"

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set



1  
A102 FLOOR PLAN - 2ND FLOOR  
1/4" = 1'-0"

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set



1  
A103 FLOOR PLAN - 3RD FLOOR  
1/4" = 1'-0"

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set

**RENOVATION Wranglers**  
 Owner: Renovation Wranglers  
 102 E 26th St  
 Bryan, TX 77803  
 kate@renovationwranglers.com | 979.450.9969

**LKB ARCHITECTURE**  
 Architect of Record: LKB Architecture  
 2929 Allen Pkwy Suite 200  
 Houston, TX 77019  
 isa@lkbarchitecture.com | 713.425.3076

**DUDLEY**  
 Structural: Dudley  
 4102 Imperial Loop Drive  
 College Station, TX 77845  
 (979) 777-0720

**amc ENGINEERS**  
 MEP: AMC Engineers  
 508 E Jackson St # 552  
 Burnet, TX 78611  
 info@amcengineers.com



68 A104 FLOOR PLAN - ROOF 1/4" = 1'-0"

This project, like most OpeningDesign's projects, is open-source (Attribution-ShareAlike 4.0 International) - CC-BY-SA 4.0 - freely available to any party for future use, assuming the terms subject. Attribution and ShareAlike are honored.

**openingdesign**  
 Architect: OpeningDesign  
 17 S Fairchild | FL 7  
 Madison, WI 53703  
 ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set



**RENOVATION**  
Wranglers  
Architecture

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
katenearson@wranglers.com | 979.450.9969

**LKB**  
ARCHITECTURE

Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076


**DUDDLEY**  
STRUCTURE

Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS

MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International - CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




Date	Description
05.19.2022	Progress Set





6C A201 BUILDING ELEVATION - SOUTH  
3/16" = 1'-0"



6A A201 BUILDING ELEVATION - EAST  
3/16" = 1'-0"

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katherine@wranglers.com | 979.450.9969

ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076


DUDDLEY  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

openingdesign  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set



6C/A300 BUILDING SECTION - THROUGH STAIRS - LOOKING NORTH  
3/16\"/>



5A/A300 BUILDING SECTION - THROUGH STAIRS - LOOKING SOUTH  
3/16\"/>

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@time.com | 979.450.9969

ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

STRUCTURAL: DUDLEY  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

MEP: AMC ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05/19/2022	Progress Set

**RENOVATION**  
Wranglers  
Engineers

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@time.com | 979.450.9969

**LKB**  
ARCHITECTURE

Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**DUDLEY**

Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720


**amc**  
ENGINEERS

MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.



4C/A301 BUILDING SECTION - THRU BALCONY - LOOKING SOUTH  
3/16" = 1'-0"



6A/A301 BUILDING SECTION - THRU BALCONY - LOOKING NORTH  
3/16" = 1'-0"

**openingdesign**

Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set


**RENOVATION**  
Wranglers  
Engineers

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@time.com | 979.450.9969


**ARCHITECTURE**  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**STRUCTURAL**  
Structural: Dudley  
4102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**MEP**  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com



4C A302 BUILDING SECTION - THRU LARGE STUDIO - LOOKING EAST  
3/16" = 1'-0"



4C A302 BUILDING SECTION - THRU SMALL STUDIO - LOOKING EAST  
3/16" = 1'-0"



4A A302 BUILDING SECTION - EAST/WEST - LOOKING NORTH  
3/16" = 1'-0"

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**openingdesign**

Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set

**RENOVATION**  
*Wranglers*

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@rw.com | 979.450.9969

**LKB**  
ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**DUDLEY**  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com



4C A303 BUILDING SECTION - EAST/WEST - AT SOUTH BALCONIES - LOOKING SOUTH  
3/16" = 1'-0"


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**openingdesign**  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date: 05.19.2022 Description: Progress Set



6A A400 BUILDING SECTION - THRU SMALL STUDIO - LOOKING EAST - @ PARAPET WALL  
3/4" = 1'-0"


4A A400 WALL SECTION - SOUTH BALCONY  
3/4" = 1'-0"

2A A400 WALL SECTION - THRU BALCONY - RAILING  
3/4" = 1'-0"

WALL SECTIONS

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike.4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set



6A A401 BUILDING SECTION - THRU LARGE STUDIO - LOOKING EAST - DECO RAILING  
3/4" = 1'-0"

5A A401 WALL SECTION - EAST/WEST - BALCONY DECK  
3/4" = 1'-0"

3A A401 WALL SECTION - EAST/WEST2 - @ UNITS PARTITION WALL  
3/4" = 1'-0"

2A A401 BUILDING SECTION - EAST/WEST - LOOKING SOUTH - TRU WINDOWS  
3/4" = 1'-0"

WALL SECTIONS

**RENOVATION Wranglers**  
 Owner: Renovation Wranglers  
 102 E 26th St  
 Bryan, TX 77803  
 kate@renovations.com | 979.450.9969

**LKB ARCHITECTURE**  
 Architect of Record: LKB Architecture  
 2929 Allen Pkwy Suite 200  
 Houston, TX 77019  
 isa@lkbarchitecture.com | 713.425.3076


**DUDLEY**  
 Structural: Dudley  
 6102 Imperial Loop Drive  
 College Station, TX 77845  
 (979) 777-0720

**amc ENGINEERS**  
 MEP: AMC Engineers  
 508 E Jackson St # 552  
 Burnet, TX 78611  
 info@amcengineers.com

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**openingdesign**  
 Architect: OpeningDesign  
 17 S Fairchild | FL 7  
 Madison, WI 53703  
 ryan@openingdesign.com | 773.425.6456


Date	Description
05.19.2022	Progress Set




6A A402 BUILDING SECTION - EAST/WEST - AT SOUTH BALCONIES - LOOKING SOUTH - Callout 1  
 3/4" = 1'-0"



This project, like most OpeningDesign's projects, is open source. Attribution and ShareAlike are honored. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




6A A410 STAIR SECTION - LOOKING NORTH  
1/2" = 1'-0"




3A A410 STAIR SECTION - LOOKING SOUTH  
1/2" = 1'-0"

Date	Description
05.19.2022	Progress Set

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.



Section 64  
1/2" = 1'-0"



Section 68  
1/2" = 1'-0"

Date	Description
05.19.2022	Progress Set

**RENOVATION Wranglers**  
Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@rw.com | 979.450.9969


**DUDDLEY**  
Structural: Dudley  
4102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc ENGINEERS**  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com


**openingdesign**  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International—CC BY-SA 4.0)—freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set




SA A412 STAIR SECTION - LOOKING WEST  
3/4" = 1'-0"




SA A412 STAIR SECTION - LOOKING EAST  
3/4" = 1'-0"

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set




3 ELEVATION - 1 BD - KITCHEN  
3/4" = 1'-0"




4 ELEVATION - 1 BD - KITCHEN - FRIDGE  
3/4" = 1'-0"




1 UNIT PLAN - 1BD SHORT (TYPE B ADA UNIT - 1ST FLOOR ONLY)  
3/8" = 1'-0"



2 UNIT PLAN - 1BD LONG (TYPE B ADA UNIT - 1ST FLOOR ONLY)  
3/8" = 1'-0"



5 ELEVATION - BATH - LAV  
3/4" = 1'-0"



6 ELEVATION - BATH - SHOWER  
3/4" = 1'-0"






**RENOVATION**  
Wranglers  
Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Kateneason@me.com | 979.450.9969

**ARCHITECTURE**  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**DUDDLEY**  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




**openingdesign**  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456


Date	Description
05.19.2022	Progress Set

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set



3 ELEVATION - END UNIT - KITCHEN  
3/4" = 1'-0"



1 UNIT PLAN - END UNIT W/ RISER ROOM (TYPE B ADA UNIT - 1ST FLOOR ONLY)  
3/8" = 1'-0"



2 UNIT PLAN - END UNIT (TYPE B ADA UNIT - 1ST FLOOR ONLY)  
3/8" = 1'-0"



Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katieeason@time.com | 979.450.9969



ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076




Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720




MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




6D SECTION DETAIL AT DOOR HEADER  
3" = 1'-0"



6B SECTION DETAIL AT DOOR SILL - 1ST FLOOR  
3" = 1'-0"



4C SECTION DETAIL AT PORCH ROOF AND PARAPET  
3" = 1'-0"



6A SECTION DETAIL AT UNIT DOOR SILL (2ND OR 3RD FLOOR)  
3" = 1'-0"




Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456


Date	Description
05.19.2022	Progress Set

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


Date	Description
05.19.2022	Progress Set



6C A501 PLAN DETAIL AT SOUTH BALCONY - ABOVE DECKING  
3" = 1'-0"



3C A501 PLAN DETAIL AT SOUTH BALCONY - AT LEDGER  
3" = 1'-0"




3A A501 PLAN DETAIL AT SOUTH BALCONY - AT STEEL  
3" = 1'-0"



This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set




6A A502 SECTION (ELEVATION) DETAIL AT SOUTH BALCONY - LOOKING EAST OR WEST  
3" = 1'-0"


5A A502 SECTION DETAIL AT SOUTH BALCONY - LOOKING EAST OR WEST  
3" = 1'-0"

2A A502 SECTION AT BALCONY 4  
3" = 1'-0"


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




2C SECTION DETAIL - ROOF HATCH  
3\"/>




6A SECTION DETAIL - PARTY WALL AND FLOOR TRUSS  
3\"/>




4A SECTION DETAIL - EXTERIOR WALL & FLOOR TRUSS  
3\"/>




SECTION DETAIL AT OUTRIGGER 1 1/2" = 1'-0"




SECTION DETAIL - TOP OF PARAPET 3" = 1'-0"




SECTION DETAIL - AT PARAPET WALL 3" = 1'-0"




SECTION DETAIL - AT ROOF BEAM 3" = 1'-0"




SECTION DETAIL - AT SOFFIT AND ALCOVE 3" = 1'-0"



SECTION DETAIL - ALCOVE AT ROOF BEAM 3" = 1'-0"




SECTION DETAIL - AT ROOF BEAM 3" = 1'-0"




SECTION DETAIL - ALCOVE AT ROOF BEAM 3" = 1'-0"

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International License). It is freely available to any party for future use, assuming the terms of the license are honored.


Date	Description
05.19.2022	Progress Set




4D A505 DETAIL - ROOF - C CHANNEL PLAN  
3" = 1'-0"




4D A505 DETAIL - ROOF - C CHANNEL SECTION 2  
3" = 1'-0"




4B A505 DETAIL - ROOF - C CHANNEL SECTION 1  
3" = 1'-0"



4B A505 DETAIL - ROOF 2 - C CHANNEL PLAN  
3" = 1'-0"



2B A505 DETAIL - ROOF 2 - C CHANNEL - SECTION 2  
3" = 1'-0"




4A A505 DETAIL - ROOF 2 - C CHANNEL - SECTION 1  
3" = 1'-0"


This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike, 4.0 International - CC BY-SA 4.0) - is freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

DOOR SCHEDULE - TYPE												
Count	Type Mark	Type	Width	Height	Fire Rating	Door Type	Door Material	Frame Type	Frame Material	GS_Door_Glazing_Material (SFI)	Comments	Type Comments
28	D1	SINGLE - LITE - MUNTINS - 3-0 x 6-8	3'-0"	6'-8"		B1	CW - CLAD WOOD DOOR	A	CW - CLAD WOOD DOOR	GL - TEMPERED - INSULATED - LOW-E		
24	D2	SINGLE - FLUSH - 3-0 x 6-8	3'-0"	6'-8"		A1	WD - HOLLOW CORE	A	WD	-		
30	D3	SINGLE - FLUSH - 2-10 x 6-8	2'-10"	6'-8"		A1	WD - HOLLOW CORE	A	WD	-		
11	D4	SINGLE - FLUSH - 2-0 x 6-8	2'-0"	6'-8"		A1	WD - HOLLOW CORE	A	WD	-		
6	D5	DOUBLE - FLUSH - 5-0 x 6-8	5'-0"	6'-8"		A2	WD - HOLLOW CORE	A	WD	-		
1	D6	SINGLE - HOLLOW METAL - 3-0 x 6-8	3'-0"	6'-8"		A1	HM	A	HM	N/A		


SIMPLIFIED WINDOW SCHEDULE						
PHASE CREATED	TYPE MARK	TYPE	COUNT	WIDTH	HEIGHT	TYPE COMMENTS
1ST PHASE	W1	DOUBLE HUNG - 2642	47	2'-5 5/8"	6'-4 7/8"	BOTTOM SASH LIMITED TO 4" MAX OPEN
1ST PHASE	W2	DOUBLE HUNG - 1842	31	1'-9 5/8"	6'-4 7/8"	BOTTOM SASH LIMITED TO 4" MAX OPEN
1ST PHASE	W3	PICTURE - 2626	18	2'-5 1/2"	2'-5 1/2"	



1 A600 DOORS - PANEL TYPES  
1/4" = 1'-0"



2 A600 DOORS - FRAME TYPES  
1/4" = 1'-0"



3 A600 WINDOW TYPES  
1/4" = 1'-0"

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katheneason@wrangler.com | 979.450.9969



ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Parkway Suite 200  
Houston, TX 77019  
lisa@lkbarchitecture.com | 713.425.3076



Structure: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720



MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com



Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description
05.19.2022	Progress Set

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)—freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**RENOVATION**  
Wranglers  
Architects


Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katherine@rwa.com | 979.450.9969

**ARCHITECTURE**  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076


**DUDDLEY**  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS


MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com




2D ADA - TYPE A - WATER CLOSET - FRONT  
1/2" = 1'-0"




3D ADA - TYPE A - WATER CLOSET - SIDE  
1/2" = 1'-0"




4D ADA - TYPE A - WATER CLOSET - FLOOR PLAN (OR TYPE B FRONT APPROACH)  
1/2" = 1'-0"




5D ADA - TYPE A - LAVATORY - SIDE (OR TYPE B FRONT APPROACH)  
1/2" = 1'-0"




6D ADA - TYPE A - LAVATORY - FRONT (OR TYPE B FRONT APPROACH)  
1/2" = 1'-0"



2C ADA - TYPE A & B - BATH - NON-CONTROL SIDE  
1/2" = 1'-0"




3C ADA - TYPE A & B - BATH - FRONT  
1/2" = 1'-0"




4C ADA - TYPE A & B - BATH - CONTROLS SIDE  
1/2" = 1'-0"




3B ADA - TYPE B - WATER CLOSET - FRONT  
1/2" = 1'-0"




4B ADA - TYPE B - WATER CLOSET - SIDE  
1/2" = 1'-0"




5B ADA - TYPE B - WATER CLOSET - FLOOR PLAN  
1/2" = 1'-0"




4B ADA - TYPE B - LAVATORY - PLAN  
1/2" = 1'-0"



6A ADA - TYPE B - LAVATORY - FRONT  
1/2" = 1'-0"



4A ADA - TYPE A & B - SHOWER - BACK  
1/2" = 1'-0"



5A ADA - TYPE A & B - SHOWER - SIDE  
1/2" = 1'-0"

GENERAL NOTES:  
• NOTE: PER IBC1210.2.2 WALLS AND PARTITIONS WITHIN 2 FEET (610MM) OF SERVICE SINKS, URINALS AND WATER CLOSETS SHALL HAVE A SMOOTH, HARD, NONABSORBENT SURFACE TO A HEIGHT OF NOT LESS THAN 4 FEET (1219 MM) ABOVE THE FLOOR, AND EXCEPT FOR STRUCTURAL ELEMENTS, THE MATERIAL USED IN SUCH WALLS SHALL BE OF A TYPE THAT IS NOT ADVERSELY AFFECTED BY MOISTURE  
• THESE ADA CLEARANCES AND GRAB BAR BLOCKING ARE ONLY REQUIRED FOR THE 1ST FLOOR UNIT

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set

**openingdesign**

Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

**PARTITION TAG NOMENCLATURE**

- 1ST LETTER = CORE MATERIAL**
  - W= WOOD
  - M=METAL
  - C=CONCRETE
  - B=MASONRY BLOCK
- 2ND LETTER = SIZE OF CORE**
  - WOOD: NOMINAL STUD SIZES (EX: 4 = 3 1/2")
  - METAL STUD: (EX 358 = 3 5/8")
  - CONCRETE: ACTUAL WALL THICKNESS (EX: 8 = 8")
  - MASONRY: NOMINAL BRICK MODULES (EX: 8 = 7 5/8")
- 3RD LETTER = LAYER MATERIAL**

	LAYER MATERIAL (3RD LETTER)						
	LAYER 3	LAYER 2	LAYER 1	CORE	LAYER 1	LAYER 2	LAYER 3
A=	-	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	STUDS 16" O.C. (20 GA. IF METAL)	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	-	-
B=	-	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	STUDS 16" O.C. (20 GA. IF METAL) BATT INSULATION	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	-	-
C=	-	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	STUDS 16" O.C. (20 GA. IF METAL)	(PROVIDE 1/4" AIR GAP IF AGAINST CONCRETE OR MASONRY)	-	-
D=	-	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	STUDS 16" O.C. (20 GA. IF METAL) BATT INSULATION	(PROVIDE 1/4" AIR GAP IF AGAINST CONCRETE OR MASONRY) - USE TREATED WOOD STUDS IF IN CONTACT WITH CONCRETE/MASONRY	-	-
G=	-	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	SEE WALL STUD SCHEDULE - STRUCT. DWGS	1" AIR GAP (PART OF A DOUBLE STUD WALL)	-	-
H=	-	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	SHEATHING - SEE STRUCT. DWGS	SEE WALL STUD SCHEDULE - STRUCT. DWGS	1" AIR GAP (PART OF A DOUBLE STUD WALL)	-	-
Q=	FIBER CEMENT - CLAPBOARD SIDING	DRAINAGE WRAP - ASTM 2273	SHEATHING - SEE STRUCT. DWGS	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL	-	-
R=	FIBER CEMENT - BATTEN AND BOARD SIDING	DRAINAGE WRAP - ASTM 2273	SHEATHING - SEE STRUCT. DWGS	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL & SHEATHING LAYER, IF AT PARTY WALL (SEE STRUCT DWGS)	-	-
S=	7/8" CORRUGATED METAL SIDING	DRAINAGE WRAP - ASTM 2273	SHEATHING - SEE STRUCT. DWGS	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL & SHEATHING LAYER, IF AT PARTY WALL (SEE STRUCT DWGS)	-	-
T=	FIBER CEMENT - CLAPBOARD SIDING	DRAINAGE WRAP - ASTM 2273	5/8" FIBERGLASS MAT GYPSUM SHEATHING	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL & SHEATHING LAYER, IF AT PARTY WALL (SEE STRUCT DWGS)	-	-
U=	FIBER CEMENT - BATTEN AND BOARD SIDING	DRAINAGE WRAP - ASTM 2273	5/8" FIBERGLASS MAT GYPSUM SHEATHING	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL & SHEATHING LAYER, IF AT PARTY WALL (SEE STRUCT DWGS)	-	-
V=	7/8" CORRUGATED METAL SIDING	DRAINAGE WRAP - ASTM 2273	5/8" FIBERGLASS MAT GYPSUM SHEATHING	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" GYP. BD OR CEMENT BACKERBOARD ON WET WALL & SHEATHING LAYER, IF AT PARTY WALL (SEE STRUCT DWGS)	-	-
W=	7/8" CORRUGATED METAL SIDING	DRAINAGE WRAP - ASTM 2273	SHEATHING - SEE STRUCT. DWGS	SEE WALL STUD SCHEDULE - STRUCT. DWGS	SHEATHING - SEE STRUCT. DWGS	DRAINAGE WRAP - ASTM 2273	7/8" CORRUGATED METAL SIDING
X=	7/8" CORRUGATED METAL SIDING	DRAINAGE WRAP - ASTM 2273	5/8" FIBERGLASS MAT GYPSUM SHEATHING	SEE WALL STUD SCHEDULE - STRUCT. DWGS	5/8" FIBERGLASS MAT GYPSUM SHEATHING	DRAINAGE WRAP - ASTM 2273	7/8" CORRUGATED METAL SIDING
Z=	-	-	16 GA PERFORATED GALV. STEEL	2.5" 12GA. STRUCTURAL METAL STUD - C/P90 GALV.	-	-	-

**4TH NUMBER: FIRE RATING**


- 0=0 HOUR
- 1=1 HOUR
- 2=2 HOUR
- 3=3 HOUR
- 5=5/8 HOUR

**5TH (AND BEYOND) LETTERS = MODIFIERS**


- A=PARTIAL HEIGHT PARTITION (WALL LAYER 1, 2, & 3 TO EXTEND 4" ABOVE FINISHED CEILING HEIGHT)
- B=PARTIAL HEIGHT WALL (WALL LAYER 1, 2, & 3 TO TERMINATE AT OR BELOW HUNG CEILING)
- D=FULL HEIGHT TO UNDERSIDE OF STRUCTURAL DECK/SHEATHING (CORE AND WALL LAYER 1, 2, & 3 TO TERMINATE AT STRUCTURAL DECK)
- F=FULL HEIGHT TO THE BOTTOM OF STRUCTURE
- K=KNEE WALL PARTITION
- R=FURRED OUT WALL

**EXAMPLE: M358B0AR**


- M=METAL
- 358=3 5/8" METAL STUD
- B=20 GA METAL STUDS 16" O.C. W/ BATT INSULATION
- 0=0 HOUR
- A=PARTIAL HEIGHT PARTITION (WALL LAYER 1, 2, & 3 TO EXTEND 4" ABOVE FINISHED CEILING HEIGHT)
- R=FURRED OUT WALL



1 A800 FLOOR/CEILING ASSEMBLY - L521  
1 1/2" = 1'-0"



4A A800 W/C/J OF FULL HEIGHT PARTITION  
3" = 1'-0"



2 A800 W4(5D) PARTY WALL - 1 HR RATED WALL (ONLY 1/2 HR IS REQUIRED)  
3" = 1'-0"


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set









1/2" CONSTRUCTION JOIST W/ SURFACE SEALANT, DOWEL MONUMENT SIGN FOOTING TO GRADE BEAM WITH (4) #6X2'-0" (2 TOP AND BOTTOM)

48 S3.1 STRUCTURAL - FOUNDATION  
1/4" = 1'-0"

SHEARWALL HOLDDOWN AT FOUNDATION						
TYPE MARK	TYPE	HARDWARE	END POST	ATTACHMENT TO END POST	ANCHORAGE TO FOUNDATION	CAPACITY
HD2	POST-INSTALLED HOLDDOWN	SIMPSON HTS	(2)-2X	(24) 0.148 X 3 NAILS	5/8" DIA. GR.36 ALL-THREAD WITH 8" EMBEDMENT WITH NUT AND WASHER	SEE SHEET S4.3 FOR DETAILS 4670
HD2	POST-INSTALLED HOLDDOWN	SIMPSON STD14	(2)-2X	(30) 0.148 X 3 NAILS	ANCHOR CAST INTO FOUNDATION	SEE SHEET S4.3 FOR DETAILS 4210
HD3	POST-INSTALLED HOLDDOWN	SIMPSON HDU8-SDS2.5	(3)-2X	(20) 1/4" X 2 1/2" SDS SCREWS	7/8" DIA. GR.36 ALL-THREAD WITH 17 1/2" EMBEDMENT WITH NUT AND WASHER	SEE SHEET S4.3 FOR DETAILS 6200
HD4	POST-INSTALLED HOLDDOWN	SIMPSON HDU14-SDS2.5	6X6	(36) 1/4" X 2 1/2" SDS SCREWS	1" DIA. GR.36 ANCHOR ROD WITH 18" EMBEDMENT	SEE SHEET S4.3 FOR DETAILS 10000

- STRUCTURAL CONNECTION NOTES:**
- MINIMUM EDGE DISTANCE TO CENTERLINE OF BOLT IS 3". AT CORNERS, THE OPPOSING EDGE DISTANCE MUST BE ≥ 6".
  - MINIMUM #4X3" LONG REINFORCING BAR LOCATED 3"-5" BELOW THE TOP OF THE SLAB IS REQUIRED TO BE CENTERED ON THE HOLDDOWN. AT CORNER, BEND THE BAR 90° AT THE CENTER
  - REFERENCE MECHANICALLY LAMINATED BUILT-UP COLUMN FOR NAILING REQUIREMENTS FOR END POST.
  - SIMPSON ATR(REQUIRED Ø) WITH SIMPSON SET-3G IS AN ACCEPTABLE OPTION.

FOOTING SCHEDULE								
TYPE MARK	NAME	COUNT	DIMENSIONS			BOTTOM REINFORCING		TYPE COMMENTS
			WIDTH	LENGTH	DEPTH	LONG	SHORT	
FT1	CONCRETE STEEL COLUMN FOOTING - 4' X 4' X 2'-6"	12	4'-0"	4'-0"	2'-6"	SEE DETAIL 28/S3.1	SEE DETAIL 28/S3.1	
FT2	CONCRETE STEEL COLUMN FOOTING 5.5' X 5.5' X 2.5'	4	5'-6"	5'-6"	2'-6"	SEE DETAIL 28/S3.1	SEE DETAIL 28/S3.1	

PTI PARAMETERS	
E <sub>m</sub> - CENTER	4.8"
E <sub>m</sub> - EDGE	2.0"
Y <sub>m</sub> - CENTER	1.0"
Y <sub>m</sub> - EDGE	1.25"
EFFECTIVE PLASTICITY INDEX	35
ALLOW. BEARING (PSF)	1,800 PSF
MIN. BEAM EMBEDMENT BELOW FINAL GRADE	18"
MIN PERIMETER BEAM EMBEDMENT BELOW FINAL GRADE	52"

SLAB GEOMETRY	
AREA (SF)	5711 SF
PERIMETER (FT)	396 FT
SHAPE FACTOR (PERIMETER <sup>2</sup> /AREA)	27.5

FOUNDATION SCHEDULE									
BEAM ID	DESCRIPTION	WIDTH	DEPTH	TOP BARS	BOTTOM BARS	STIRRUPS	Type	Comments	OD Structural
GB1	GRADE BEAM - INTERIOR - 14"	14"	30"	(3) - #6	(3) - #6	#3 @24" OC	F		F
GB2	GRADE BEAM - PERIMETER - 14"	14"	30"	(3) - #6	(3) - #6	#3 @24" OC	F		F
GB2A	GRADE BEAM - PERIMETER - 14" - W/ 8" CONCRETE WALL	8"		(3) - #6	(3) - #6	#3 @24" OC	F	SEE 1D/S3.1 FOR MORE DETAIL	F
GB3	GRADE BEAM - INTERIOR - 28"	28"	30"	DOUBLE GB1	DOUBLE GB1	DOUBLE GB1	F	(2) GB1 STIRRUP CAGES SIDE/SIDE - SEE DETAIL 2A/S3.0	F
GB4	8" CONCRETE FOUNDATION	8"	36"				F	SEE 6A/S3.1	F
GB5	TURNDOWN THICKENED SLAB	12"	12"	N/R	(2) - #4	N/R	F		F

FOUNDATION NOTES	
FOUNDATION TYPE:	BRAB TYPE III - STIFFENED NON-STRUCTURAL SLAB-ON-GROUND
SLAB THICKNESS:	5"
SLAB REINFORCEMENT:	#4 @ 14" OC EACH WAY - REF DETAIL
DESIGN METHOD:	ACI 318
VAPOR RETARDER:	MINIMUM 10 MIL (LENGTH THICKER REQ'D BY ARCHITECT)

- NOTES:**
- BEAMS ARE TYPE B1 UNO.
  - LOCATE THE FIRST STIRRUP A MAXIMUM OF 3" FROM FACE OF SUPPORT.
  - BEAM DEPTH INDICATED IN THE SCHEDULE IS A STRUCTURAL MINIMUM THAT THE BEAM REINFORCEMENT CAGE MAY BE BASED UPON. REFERENCE GEOTECHNICAL REPORT FOR MINIMUM GRADE BEAM EMBEDMENT BELOW ADJACENT FINAL GRADE OR FLATWORK/PAVEMENT.
  - N/R = NOT REQUIRED

- PLAN NOTES**
- VERIFY ALL EDGE OF FOUNDATION DIMENSIONS WITH FINAL ARCHITECTURE FLOOR PLANS.
  - FORM DIMENSIONS: SLAB DROPS, SLOPES, ETC. SHOWN AS AN AID TO CONTRACTOR ONLY. VERIFY EXACT DIMENSIONS AND LOCATIONS WITH ARCHITECT.
  - DIMENSIONS ARE TO OF GRADE BEAMS OR EDGE OF SLAB UNLESS NOTED OTHERWISE.
  - CONTROL JOINTS (SAW-CUTS) ARE RECOMMENDED TO REDUCE CRACKS IN THE SLAB, BUT ARE NOT REQUIRED FOR STRUCTURAL REQUIREMENTS. FOR THE RECOMMENDED MAXIMUM JOINT SPACING REFERENCE DETAIL.
  - FOR FLATWORK OR PAVEMENT ABUTTING THE BUILDING FOUNDATION REFERENCE DETAIL.
  - CONCRETE IS ASSUMED TO RECEIVE A STEEL TROWEL FINISH UNLESS NOTED OTHERWISE. NOTIFY ENGINEER IF ARCHITECTURALLY EXPOSED CONCRETE (STAINED, POLISHED, ETC.) IS PLANNED FOR ADDITIONAL SHRINKAGE CRACKING MITIGATION METHODS.

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**RENOVATION**  
Architects

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katerencason@re.com | 979.450.9969


**ARCHITECTURE**  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**DUDDLEY**  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720


**amc**  
ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

SUBGRADE AND BUILDING PAD NOTES (PER GEOTECHNICAL REPORT):


- SUBGRADE IMPROVEMENT:
  - PROVIDE MINIMUM 2 FEET SELECT FILL TO TOP OF BUILDING PAD ELEVATION. THE SELECT FILL PAD MUST BE OF UNIFORM THICKNESS UNDO BY GEOTECHNICAL ENGINEER.
- SITE PREPARATION:
  - SOFT SOILS SHOULD BE REMOVED UNTIL FIRM SOIL IS REACHED. THE SOFT SOILS CAN BE AERATED AND PLACED BACK IN SIX-INCH LOOSE LIFTS AND COMPACTED TO 95% AS SPECIFIED BY ASTM D-698. TREE STUMPS, TREE ROOTS, OLD SLABS, OLD FOUNDATIONS AND EXISTING PAVEMENTS SHOULD BE REMOVED FROM THE STRUCTURE AREA. IF THE TREE STUMPS AND ROOTS ARE LEFT IN PLACE, SETTLEMENT AND TERMITE INFESTATION MAY OCCUR. ONCE A ROOT SYSTEM IS REMOVED, A VOID IS CREATED IN THE SUBSOIL. IT IS RECOMMENDED TO FILL THESE VOIDS WITH STRUCTURAL FILL OR CEMENT-STABILIZED SAND AND COMPACT TO 95% AS SPECIFIED BY ASTM D-698.
  - ANY LOW-LYING AREAS INCLUDING RAVINES, DITCHES, SWAMPS, ETC. SHOULD BE FILLED WITH STRUCTURAL FILL AND PLACED IN EIGHT-INCH LIFTS. EACH LIFT SHOULD BE COMPACTED TO 95% OF THE MAXIMUM DRY DENSITY AS SPECIFIED BY ASTM D-698.
  - THE EXPOSED SUBGRADE SHOULD BE SCARIFIED TO A MINIMUM DEPTH OF SIX (6) INCHES FOUNDATION AREAS OR PER SUBGRADE IMPROVEMENT REQUIREMENTS. THE SUBGRADE SHOULD THEN BE COMPACTED TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE STANDARD MOISTURE DENSITY RELATIONSHIP (ASTM D-698). IN THE EVENT THAT THE UPPER SIX (6) INCHES CANNOT BE COMPACTED DUE TO EXCESSIVE MOISTURE, WE RECOMMEND THAT THESE SOILS BE EXCAVATED AND REMOVED OR CHEMICALLY STABILIZED TO PROVIDE A FIRM BASE FOR FILL PLACEMENT. PROOF-ROLLING SHOULD BE PERFORMED USING A HEAVY TIRED LOADED TRUCK OR PNEUMATIC RUBBER-TIRED WEIGHING 20 TONS.
  - THE SELECT FILL SOILS SHALL BE LIMITED TO THE FOOTPRINT OF THE FOUNDATION. IF OVERBUILD IS REQUIRED, INSTALL HORIZONTAL CLAY CAP TO COVER THE FILL OVERBUILD, BEYOND THE PERIMETER OF THE STRUCTURE.
  - THE FLOOR SLAB SHOULD BE PLACED AS SOON AS POSSIBLE AFTER THE BUILDING PAD IS PREPARED. IF THE BUILDING PAD IS LEFT EXPOSED TO RAINFALL, PERCHED GROUNDWATER CONDITIONS MAY DEVELOP WHICH WILL UNDERMINE THE INTEGRITY OF THE FLOOR SLAB. ALL TRENCHES (WATER, CABLE, ELECTRICAL) SHOULD BE PROPERLY BACKFILLED AND COMPACTED TO 95% OF THE MAXIMUM DRY DENSITY. SAND OR PERMEABLE MATERIALS SHOULD NOT BE USED AS BACKFILL. IMPROPERLY BACKFILLED AND IMPROPERLY COMPACTED TRENCH, IF LEFT EXPOSED WILL ALSO BE ANOTHER SOURCE FOR PERCHED GROUNDWATER CONDITIONS. IN GENERAL, PERCHED WATER TENDS TO BE TRAPPED WITHIN THE FILL. THE TRAPPED GROUNDWATER TENDS TO SOFTEN THE SUBGRADE. POSITIVE DRAINAGE SHOULD BE MAINTAINED ACROSS THE ENTIRE BUILDING PAD.
  - A QUALIFIED SOIL TECHNICIAN SHOULD MONITOR ALL EARTHWORK OPERATIONS. FIELD DENSITY TESTS SHOULD BE CONDUCTED ON EACH LIFT USING A NUCLEAR DENSITY GAUGE. THE GAUGE SHOULD BE CALIBRATED EVERY DAY. PRIOR TO FIELD DENSITY TESTS, A 50-POUND SAMPLE FROM THE SUBGRADE SOILS SHOULD BE OBTAINED. A SIMILAR SAMPLE SHOULD BE OBTAINED FROM THE FILL SOILS. A STANDARD MOISTURE DENSITY RELATIONSHIP (ASTM D-698) SHOULD BE PERFORMED ON EACH SAMPLE IN ORDER TO OBTAIN AN OPTIMUM MOISTURE CONTENT AND A MAXIMUM DRY DENSITY. THE FIELD DENSITY TESTS SHOULD BE COMPARED TO THESE RESULTS EVERY TIME THE SOILS ARE TESTED IN THE FIELD.
- LOW SWELL POTENTIAL STRUCTURAL FILL (SELECT FILL)
  - LOW SWELL POTENTIAL SELECT FILL SHOULD CONSIST OF COHESIVE SOILS FREE OF ORGANICS OR OTHER DELETERIOUS MATERIALS AND SHOULD HAVE A PLASTICITY INDEX NOT LESS THAN 7 OR MORE THAN 20. SANDY CLAYEY ARE RECOMMENDED FOR USE. THE LOW SWELL POTENTIAL SELECT FILL SHOULD BE CLEANED AND FREE OF ORGANIC MATTER OR OTHER DELETERIOUS MATERIAL. THE FILL SHOULD BE PLACED IN MAXIMUM SIX-INCH LOOSE LIFTS AND COMPACTED TO A MINIMUM OF 95 PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D 698 (STANDARD PROCTOR). THE MOISTURE CONTENT AT THE TIME OF COMPACTION SHOULD BE -2% +3% OF THE OPTIMUM VALUE AS DEFINED BY ASTM D 698. THE REFERENCED MOISTURE CONTENT AND DENSITY SHOULD BE MAINTAINED UNTIL CONSTRUCTION IS COMPLETE.
- HORIZONTAL MOISTURE BARRIER
  - WHERE THE PERIMETER OF THE FOUNDATION DOES NOT HAVE LOW PERMEABILITY FLATWORK (SIDEWALK, PAVEMENT, PATIO, ETC.) ADJUTING THE FOUNDATION, A HORIZONTAL MOISTURE BARRIER VIA CLAY CAP AND VAPOR RETARDER MUST BE PROVIDED.
    - CLAY CAP: A MINIMUM 5" WIDE LOW PERMEABILITY CLAY "CAP" SHALL BE PLACED ALONG THE EXTERIOR OF THE FOUNDATION TO HELP MINIMIZE MOISTURE INFILTRATION INTO THE SELECT FILL SOIL PADS. THE LOW PERMEABILITY, 1-FOOT THICK CLAY "CAP" SHALL HAVE A MINIMUM PLASTICITY INDEX (PI) OF 30.
    - VAPOR RETARDER: BELOW THE CLAY CAP, A MIN 10 MIL VAPOR RETARDER MUST BE PROVIDED ON A MINIMUM 5% SLOPE. RETARDER MUST BE SECURED TO THE FOUNDATION.
- DRAINAGE
  - ROOF DRAINAGE SHOULD BE COLLECTED BY A SYSTEM OF GUTTERS AND DOWN SPOUTS AND TRANSMITTED A MINIMUM DISTANCE OF 5' AWAY FROM THE FOUNDATION TO AN AREA WITH POSITIVE DRAINAGE AWAY FROM THE FOUNDATION. PREFERABLY TO A PAVED SURFACE WHERE WATER CAN DRAIN RAPIDLY AWAY FROM THE STRUCTURE, SIDEWALKS, PARKING AREAS, BUILDING ACCESS DRIVES, AND THE GENERAL GROUND SURFACE SHOULD BE SLOPED SO THAT WATER WILL DRAIN AWAY FROM THE STRUCTURE. WATER SHOULD NOT BE ALLOWED TO POND NEAR THE BUILDING FOUNDATIONS.
  - FINAL GRADES SHALL SLOPE A MINIMUM OF 5% FOR THE FIRST 10 FEET AWAY FROM THE FOUNDATION IN ALL DIRECTIONS. THIS SLOPE SHALL OCCUR IN THE SELECT FILL OR IN-SITU SOIL. MERELY SLOPING TOPSOIL IS NOT SUFFICIENT.
- LANDSCAPING
  - AVOID THE USE OF METAL EDGING OR OTHER DAMMING DEVICES WITHIN FIVE FEET OF THE FOUNDATION. THE ROOTS OF TREES AND LARGE PLANTS REMOVE LARGE QUANTITIES OF WATER FROM THE SOIL. IF THESE TREES AND SHRUBS ARE NEAR THE FOUNDATION AND IF SUFFICIENT WATER IS NOT SUPPLIED, THE SOILS MAY SHRINK UP EXPANSIVE, CAUSING SUBSIDENCE IN THE FOUNDATION. DURING DRY PERIODS, ENOUGH WATER SHOULD BE SUPPLIED TO TREES TO MINIMIZE SHRINKING OF EXPANSIVE SOILS AROUND THEM. MOST OF THE IRRIGATION WATER SHOULD BE APPLIED WELL AWAY FROM THE FOUNDATION TO ATTRACT THE TREE ROOTS IN THAT DIRECTION. WHEN TREES MATURE TO THE POINT OF SHADING THE ENTIRE LOT, REGULAR PRUNING WILL BE NEEDED TO REDUCE THEIR WATER UPTAKE. LANDSCAPING PLANTS, SHRUBS, FLOWERS, ETC.] SHOULD NOT TRAP WATER AGAINST THE FOUNDATION. PROVIDE A SLOPE IN SOILS BELOW LANDSCAPE BEDDING AND IN THE BEDDING AWAY FROM THE FOUNDATION. ALTERNATIVELY, PROVIDE SWALES AROUND AND THROUGH THE LANDSCAPING TO DRAIN WATER AWAY. PROVIDE UNIFORM GROUND COVER AROUND THE FOUNDATION. THIS WILL HELP KEEP THE MOISTURE EVAPORATION RATE UNIFORM. IN AREAS THAT ARE NOT PLANTED, USE MULCH. EXTEND THE GROUND COVER AT LEAST FIVE FEET FROM THE FOUNDATION.
  - ANY ALL TREES SHALL BE PLANTED AT A MINIMUM DISTANCE EQUIVALENT TO THE HEIGHT OF THE TREE OR THE DRIP LINE PLUS 10 FEET WHICHEVER IS GREATER.
- SOIL MOISTURE
  - EXPANSIVE SOILS HEAVE AND SUBSIDE DUE TO CHANGES IN MOISTURE CONTENT. CHANGES IN MOISTURE CONTENT CAN CAUSE VERY LARGE CHANGES IN SOIL VOLUME WHEN GOING FROM A DRY TO A SATURATED CONDITION, AND VICE VERSA. THIS MOVEMENT DOES NOT MEAN THE FOUNDATION IS IMPROPERLY DESIGNED OR THAT IT HAS FAILED. THE FOUNDATION DESIGN ENGINEER CANNOT CONTROL THE MOISTURE CONTENT OF THE SOIL, BUT OFTEN THE OWNER/TENANT CAN. UNIFORMITY IS THE KEY: UNIFORM MOISTURE CONTENT IN THE SOIL, UNIFORMLY MAINTAINED IN ALL AREAS AROUND THE FOUNDATION. IF CHANGES IN MOISTURE CONTENT ARE UNIFORM, THEN MOVEMENT OF THE FOUNDATION WILL BE UNIFORM AND LESS DISTRESS WILL BE CREATED IN THE STRUCTURE. IF CHANGES IN MOISTURE CONTENT ARE NON-UNIFORM, THEN THERE MAY BE DIFFERENTIAL MOVEMENT IN THE FOUNDATION. DIFFERENTIAL MOVEMENT CAN CAUSE GREATER (AND MORE OBVIOUS) DISTRESS IN THE STRUCTURE, LEAKING POOLS, LEAKING PLUMBING LINES, LEAKING DRAINS, DRIPPING FAUCETS, DRIPPING AIR CONDITIONING CONDENSATE LINES, AND MISDIRECTED WATER FROM CLOGGED AND BROKEN GUTTERS AND DOWNSPOUTS CAN CAUSE LOCAL HIGH MOISTURE CONTENTS THAT CAN RESULT IN DIFFERENTIAL MOVEMENT IN AREAS OF EXPANSIVE SOILS. THESE CONDITIONS SHOULD BE REMEDIED AS SOON AS POSSIBLE. TREES IN OR NEAR THE FOOTPRINT OF THE FOUNDATION, EITHER REMOVED OR PLANTED DURING CONSTRUCTION, CAUSE THE MAJORITY OF FOUNDATION PROBLEMS REQUIRING REPAIR IN THIS AREA. TREES REMOVED DURING CONSTRUCTION TEND TO CAUSE HEAVE OF EXPANSIVE SOILS DURING THE FIRST FEW YEARS, WITH INITIAL DISTRESS OFTEN EVIDENT AT THE TIME OF MOVE-IN. TREES PLANTED DURING OR AFTER CONSTRUCTION TEND TO CAUSE SUBSIDENCE OF EXPANSIVE SOILS. HOWEVER, SIGNIFICANT SUBSIDENCE DISTRESS WILL USUALLY NOT OCCUR FOR TEN TO TWENTY YEARS AS THE TREES MATURE.
- CLIMATE
  - DURING PERIODS OF DRY WEATHER, THE SOIL AROUND THE FOUNDATION SHOULD BE IRRIGATED IF THE BUILDING IS LOCATED IN AN AREA WHERE EXPANSIVE SOILS ARE KNOWN TO OCCUR. THE MOST COMMONLY USED IRRIGATION SYSTEM IS ABOVEGROUND TINED SPRINKLERS WITH A MANUAL OVERRIDE SO THEY CAN BE TURNED OFF IN RAINY WEATHER. AN AUTOMATIC BELOWGROUND IRRIGATION SYSTEM THAT SENSES THE MOISTURE CONTENT OF THE SOIL MAY ALSO BE USED. TEND TO KEEP THE IRRIGATION SYSTEM SET ON "MANUAL", AND ONLY USE IT DRIER PERIODS WHEN WEEDING OF THE LAWN GRASSES AND OTHER VEGETATION OCCURS. THE IRRIGATION SHOULD BE DONE AT LEAST ONE TO TWO FEET AWAY FROM THE FOUNDATION, AND THEN LIGHTLY SO THAT TREE ROOTS ARE NOT ATTRACTED THERE. DO NOT ALLOW SPRINKLERS TO SPRAY WATER AGAINST THE STRUCTURE. IN EXTENDED DRY PERIODS, SHOULD THE SOIL CRACK AND PULL AWAY FROM THE FOUNDATION, DO NOT WATER DIRECTLY INTO THE GAP.
- UTILITIES
  - CONNECTIONS FOR UTILITIES (PLUMBING, ELECTRICAL, GAS, ETC.) THAT ARE UNDERNEATH, GO THROUGH OR ARE ATTACHED TO THE FOUNDATION SHALL HAVE BE FLEXIBLE TO ACCOMMODATE FOUNDATION MOVEMENT OF AT LEAST 2". ALL DRAINAGE PIPING, AND GENERAL PLUMBING SYSTEMS ASSOCIATED WITH THE FOUNDATION OR IN PROXIMITY TO THE FOUNDATION SHALL BE LEAK TESTED FOLLOWING INSTALLATION AND ON AN ANNUAL BASIS.
- ARCHITECTURAL FINISHES
  - TILE FLOORS SHALL BE JOINTED FREQUENTLY TO MINIMIZE CRACKING.
  - WALL COVERINGS SHALL BE JOINTED ON EACH SIDE OF DOOR AND WINDOW OPENINGS.
  - ALL ARCHITECTURAL FINISHES SHALL MIRROR CONTROL, EXPANSION OR CONSTRUCTION JOINTS IN THE FOUNDATION.




1 S0.1A STRUCTURAL FOUNDATION - 3D - 1



2 S0.1A STRUCTURAL FOUNDATION - 3D - 2



6C S0.1A STRUCTURAL FRAMING - 3D - 1



4A S0.1A STRUCTURAL FRAMING - 3D - 2

**RENOVATION**  
Wranglers

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
katheneason@me.com | 979.450.9969

**DUDDLEY**

Structural: Dudley  
4102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS


MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com

**openingdesign**

Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International—CC BY-SA 4.0)—freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date	Description
05.19.2022	Progress Set



68  
S0.2 FRAMING PLAN - 2ND FLOOR  
1/4" = 1'-0"

SHEAR WALL SCHEDULE					
SHEAR WALL TYPE	SHEATHING TYPE	PANEL EDGE NAILING	FIELD NAILING	ANCHORAGE	ALLOWABLE WIND SHEAR CAPACITY
SW1	7/16" WSP	4"	12"	(5/8" Ø @ 40" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	335 PLF
SW2	7/16" WSP	4"	12"	(5/8" Ø @ 32" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	490 PLF
SW3	7/16" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 2" OC - AT WOOD)	630 PLF
SW4	15/32" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	840 PLF
SW5	15/32" WSP	2"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	991 PLF
SW6	5/8" GYP WALLBOARD	7"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	115 PLF
SW7	5/8" GYP WALLBOARD	4"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	145 PLF

- SHEAR WALL NOTES:**
- ALL FASTENERS FOR WOOD STRUCTURAL PANEL SHALL BE FLAT HEAD NAILS CONSISTING OF THE FOLLOWING UNO:
    - A. 0.131" Ø X 2 1/2" LONG
    - B. 0.148" Ø X 3" LONG
  - FASTENERS FOR GYPSUM WALLBOARD SHALL BE ONE OF THE FOLLOWING:
    - A. 6d COOLER NAILS (0.092" X 1 7/8" LONG, 1/4" HEAD)
    - B. WALLBOARD NAIL (0.0912" X 1 7/8" LONG, 1/4" HEAD)
    - C. 0.120" NAIL X 1-3/4" LONG, MIN 3/8" HEAD
  - NO. 6 TYPE S OR W DRYWALL SCREWS 1-1/4" LONG
  - ANCHORS INTO CONCRETE SHALL EITHER BE CAST-IN-PLACE J-BOLTS OR ADHESIVE ANCHORS WITH A MINIMUM EMBEDMENT OF 8". THE CONTRACTOR SHALL SUBMIT PROPOSED ADHESIVE ANCHOR ASSEMBLY FOR APPROVAL.
  - ALL PANEL EDGES SHALL BE BLOCKED.
  - WSP = WOOD STRUCTURAL PANEL. REF GENERAL NOTES FOR SPECIFICATIONS.
  - IF WALL IS SHEATHED ON BOTH SIDES, THEN SILL PLATE ANCHORAGE AND CONNECTION OF BOTTOM PLATE TO TOP PLATE SHALL BE DOUBLED.
  - PANELS MUST BE INSTALLED DIRECTLY TO FRAMING.
  - VALUES CALCULATED ARE FOR SOUTHERN PINE OR DOUGLAS-FIR LARCH FRAMING. CONTACT FOR IF OTHER SPECIES ARE USED.
  - PROVIDE 1/8" WIDE JOINTS IN SHEATHING TO ALLOW FOR SHRINKAGE AND EXPANSION OF THE PANELS.

SHEARWALL HOLDDOWNS AT ELEVATED FLOOR					
TYPE MARK	HOLDDOWN HARDWARE	END LENGTH (IN)	FASTENERS	END POST	ALLOWABLE TENSION LOAD (LBF)
ST1	(1) SIMPSON CS18	12"	(11) 0.131 X 2 1/2" NAILS	(2) - 2X	1,370
ST2	(2) SIMPSON CS18	12"	(11) 0.131 X 2 1/2" NAILS	(2) - 2X	2,740
ST3	(2) SIMPSON CS14	19"	(18) 0.131 X 2 1/2" NAILS	(3) - 2X	4,780

- SHEARWALL & HOLDDOWN NOTES:**
- MULTIPLE PLIES OF END POSTS SHALL BE FASTENED TOGETHER PER THE MECHANICALLY BUILT-UP COLUMN NAILED DETAIL.
  - REFERENCE DETAIL 6A/S4.2 FOR TYPICAL HOLDDOWN CONFIGURATIONS.


BEAM SCHEDULE					
BEAM TAG	BEAM SIZE	STUD PACK - NUMBER OF STUDS	FACE-MOUNT HANGER	TOP-FLANGE HANGER	NOTE NUMBER
B226	(3)2X6	2	LUS26-2	HU26-2TF	1,2,3,4,6,7,8,9
B328	(3)-2X8	2	LUS26-3	HU548TF	1,2,3,4,6,7,8,9
B3212	(3)-2X12	3	HU210-3	HU212-3TF	1,2,3,4,6,7,8,9
B411	GL - 3 1/2" X 11 1/4"	3	HU5410	HB3.56/11.25	3,4,5,6,7,8,9

- BEAM LEGEND NOTES:**
- MULTIPLE PLY DIMENSIONAL LUMBER BEAMS SHALL RECEIVE 1/2" PLYWOOD SHEATHING. SEE TYPICAL DETAIL.
  - FOR NAILING BUILT-UP BEAMS REFER TO DETAIL 2A/S4.0
  - FOR KING AND JACK STUD REQUIREMENTS FOR EXTERIOR HEADERS REFER TO DETAIL 4C/S4.1
  - FOR KING AND JACK STUD REQUIREMENTS IN INTERIOR HEADERS REFER TO DETAIL 5B/S4.1
  - BEAMS SHALL BE ANTHONY POWER BEAM GLUE LAMINATED BEAMS OR APPROVED EQUAL
  - STUD PACKS ARE REQUIRED WHEN BEAM IS BEARING ON A WALL ASSEMBLY. STUD PACKS MUST CONTINUE ALL THE WAY TO THE FOUNDATION UNLESS TRANSFERRED BY A BEAM.
  - ALL STUDS IN STUD PACK SHALL BE NO. 2 SOUTHERN PINE OR BETTER.
  - SHEATHING AND/OR DRYWALL MUST BE ATTACHED TO EACH INDIVIDUAL STUD IN THE STUD PACK.
  - ALL STUDS IN STUD PACK MUST BE FASTENED PER MECHANICALLY LAMINATED BUILT-UP COLUMN-NAILED - REFER TO 6A/S4.1

WALL STUD SCHEDULE				
TOP OF WALL	MAX PLATE HT	EXTERIOR WALL	INTERIOR NON-LOAD BEARING	PARTY WALL
ROOF	8" - 11 5/8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 16" O.C.
3RD	10" - 8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 12" O.C.
2ND	10" - 9 5/8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 8" O.C.

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date: 05/19/2022 Description: Progress Set


  
**openingdesign**
  
 Architect: OpeningDesign
   
 17 S Fairchild | FL 7
   
 Madison, WI 53703
   
 ryan@openingdesign.com | 773.425.6456


**RENOVATION**  
Wranglers  
ENGINEERS

Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
katenecason@re.com | 979.450.9969

**ARCHITECTURE**  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

**DUDDLEY**  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amec**  
ENGINEERS  
MEP: AMEC Engineers  
508 E Jackson St # 552  
Burrhead, TX 78611  
info@amecengineers.com



48  
S0.3  
FRAMING PLAN - 3RD FLOOR  
1/4" = 1'-0"

SHEAR WALL SCHEDULE					
SHEAR WALL TYPE	SHEATHING TYPE	PANEL EDGE NAILING	FIELD NAILING	ANCHORAGE	ALLOWABLE WIND SHEAR CAPACITY
SW1	7/16" WSP	4"	12"	(5/8" Ø @ 32" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	335 PLF
SW2	7/16" WSP	4"	12"	(5/8" Ø @ 32" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	490 PLF
SW3	7/16" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 2" OC - AT WOOD)	630 PLF
SW4	15/32" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	840 PLF
SW5	15/32" WSP	2"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	991 PLF
SW6	5/8" GYP WALLBOARD	7"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	115 PLF
SW7	5/8" GYP WALLBOARD	4"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	145 PLF

- SHEAR WALL NOTES:**
- ALL FASTENERS FOR WOOD STRUCTURAL PANEL SHALL BE FLAT HEAD NAILS CONSISTING OF THE FOLLOWING UNO:
    - A. 0.131" Ø X 2 1/2" LONG
    - B. 0.148" Ø X 3" LONG
  - FASTENERS FOR GYPSUM WALLBOARD SHALL BE ONE OF THE FOLLOWING:
    - A. 6d COOLER NAILS (0.092" X 1 7/8" LONG, 1/4" HEAD)
    - B. WALLBOARD NAIL (0.0912" X 1 7/8" LONG, 1/4" HEAD)
    - C. 0.120" NAIL X 1-3/4" LONG, MIN 3/8" HEAD
  - NO. 6 TYPE S OR W DRYWALL SCREWS 1-1/4" LONG
  - ANCHORS INTO CONCRETE SHALL EITHER BE CAST-IN-PLACE J-BOLTS OR ADHESIVE ANCHORS WITH A MINIMUM EMBEDMENT OF 8". THE CONTRACTOR SHALL SUBMIT PROPOSED ADHESIVE ANCHOR ASSEMBLY FOR APPROVAL.
  - ALL PANEL EDGES SHALL BE BLOCKED.
  - WSP = WOOD STRUCTURAL PANEL. REF GENERAL NOTES FOR SPECIFICATIONS.
  - IF WALL IS SHEATHED ON BOTH SIDES, THEN SILL PLATE ANCHORAGE AND CONNECTION OF BOTTOM PLATE TO TOP PLATE SHALL BE DOUBLED.
  - PANELS MUST BE INSTALLED DIRECTLY TO FRAMING.
  - VALUES CALCULATED ARE FOR SOUTHERN PINE OR DOUGLAS-FIR LARCH FRAMING. CONTACT FOR IF OTHER SPECIES ARE USED.
  - PROVIDE 1/8" WIDE JOINTS IN SHEATHING TO ALLOW FOR SHRINKAGE AND EXPANSION OF THE PANELS.

SHEARWALL HOLD-DOWNS AT ELEVATED FLOOR					
TYPE MARK	HOLD-DOWN HARDWARE	END LENGTH (IN)	FASTENERS	END POST	ALLOWABLE TENSION LOAD (LBF)
ST1	(1) SIMPSON CS18	12"	((11) 0.131 X 2 1/2" NAILS	(2) - 2X	1,370
ST2	(2) SIMPSON CS18	12"	((11) 0.131 X 2 1/2" NAILS	(2) - 2X	2740
ST3	(2) SIMPSON CS14	19"	((18) 0.131 X 2 1/2" NAILS	(3) - 2X	4980

- SHEARWALL & HOLD-DOWN NOTES:**
- MULTIPLE PLIES OF END POSTS SHALL BE FASTENED TOGETHER PER THE MECHANICALLY BUILT-UP COLUMN NAILED DETAIL.
  - REFERENCE DETAIL 6A/S4.2 FOR TYPICAL HOLD-DOWN CONFIGURATIONS.

BEAM SCHEDULE					
BEAM TAG	BEAM SIZE	STUD PACK - NUMBER OF STUDS	FACE-MOUNT HANGER	TOP-FLANGE HANGER	NOTE NUMBER
B226	(3)2X6	2	LUS26-2	HU26-2TF	1,2,3,4,6,7,8,9
B328	(3)-2X8	2	LUS26-3	HUS48TF	1,2,3,4,6,7,8,9
B3212	(3)-2X12	3	HU210-3	HU212-3TF	1,2,3,4,6,7,8,9
B411	GL - 3 1/2" X 11 1/4"	3	HU5410	HB3.56/11.25	3,4,5,6,7,8,9

- BEAM LEGEND NOTES:**
- MULTIPLE PLY DIMENSIONAL LUMBER BEAMS SHALL RECEIVE 1/2" PLYWOOD SHEATHING. SEE TYPICAL DETAIL.
  - FOR NAILING BUILT-UP BEAMS REFER TO DETAIL 2A/S4.0
  - FOR KING AND JACK STUD REQUIREMENTS FOR EXTERIOR HEADERS REFER TO DETAIL 4C/S4.1
  - FOR KING AND JACK STUD REQUIREMENTS IN INTERIOR HEADERS REFER TO DETAIL 5B/S4.1
  - BEAMS SHALL BE ANTHONY POWER BEAM GLUE LAMINATED BEAMS OR APPROVED EQUAL
  - STUD PACKS ARE REQUIRED WHEN BEAM IS BEARING ON A WALL ASSEMBLY. STUD PACKS MUST CONTINUE ALL THE WAY TO THE FOUNDATION UNLESS TRANSFERRED BY A BEAM.
  - ALL STUDS IN STUD PACK SHALL BE NO. 2 SOUTHERN PINE OR BETTER.
  - SHEATHING AND/OR DRYWALL MUST BE ATTACHED TO EACH INDIVIDUAL STUD IN THE STUD PACK.
  - ALL STUDS IN STUD PACK MUST BE FASTENED PER MECHANICALLY LAMINATED BUILT-UP COLUMN-NAILED - REFER TO 6A/S4.1


WALL STUD SCHEDULE				
TOP OF WALL	MAX PLATE HT	EXTERIOR WALL	INTERIOR NON-LOAD BEARING	PARTY WALL
ROOF	8" - 11 5/8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 16" O.C.
3RD	10" - 8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 12" O.C.
2ND	10" - 9/8"	2X4 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 8" O.C.

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

Date: 05/19/2022

**openingdesign**

Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456



68  
S0.4 FRAMING PLAN - ROOF  
1/4" = 1'-0"

SHEAR WALL SCHEDULE					
SHEAR WALL TYPE	SHEATHING TYPE	PANEL EDGE NAILING	FIELD NAILING	ANCHORAGE	ALLOWABLE WIND SHEAR CAPACITY
SW1	7/16" WSP	6"	12"	(5/8" Ø @ 40" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	335 PLF
SW2	7/16" WSP	4"	12"	(5/8" Ø @ 32" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	490 PLF
SW3	7/16" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 2" OC - AT WOOD)	630 PLF
SW4	1 1/2" WSP	3"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	840 PLF
SW5	1 1/2" WSP	2"	12"	(5/8" Ø @ 24" O.C. - AT CONCRETE) - (0.148" X 3" LONG NAILS @ 2" OC - AT WOOD)	991 PLF
SW6	5/8" GYP WALLBOARD	7"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	115 PLF
SW7	5/8" GYP WALLBOARD	4"	12"	(5/8" Ø @ 48" O.C. - AT CONCRETE) - (0.131" X 3" LONG NAILS @ 3" OC - AT WOOD)	145 PLF


- SHEAR WALL NOTES:**
- ALL FASTENERS FOR WOOD STRUCTURAL PANEL SHALL BE FLAT HEAD NAILS CONSISTING OF THE FOLLOWING UNO:
    - 0.131" Ø X 2 1/2" LONG
    - 0.148" Ø X 3" LONG
  - FASTENERS FOR GYPSUM WALLBOARD SHALL BE ONE OF THE FOLLOWING:
    - 6d COOLER NAILS (0.092" X 1 7/8" LONG, 1/4" HEAD)
    - WALLBOARD NAIL (0.0915" X 1 7/8" LONG, 19/64" HEAD)
    - 0.120" NAIL X 1-3/4" LONG, MIN 3/8" HEAD
    - NO. 6 TYPE S OR W DRYWALL SCREWS 1-1/4" LONG
  - ANCHORS INTO CONCRETE SHALL EITHER BE CAST-IN-PLACE J-BOLTS OR ADHESIVE ANCHORS WITH A MINIMUM EMBEDMENT OF 8". THE CONTRACTOR SHALL SUBMIT PROPOSED ADHESIVE ANCHOR ASSEMBLY FOR APPROVAL.
  - ALL PANEL EDGES SHALL BE BLOCKED.
  - WSP = WOOD STRUCTURAL PANEL. REF GENERAL NOTES FOR SPECIFICATIONS.
  - IF WALL IS SHEATHED ON BOTH SIDES, THEN SILL PLATE ANCHORAGE AND CONNECTION OF BOTTOM PLATE TO TOP PLATE SHALL BE DOUBLED.
  - PANELS MUST BE INSTALLED DIRECTLY TO FRAMING.
  - VALUES CALCULATED ARE FOR SOUTHERN PINE OR DOUGLAS-FIR LARCH FRAMING. CONTACT EOR IF OTHER SPECIES ARE USED.
  - PROVIDE 1/8" WIDE JOINTS IN SHEATHING TO ALLOW FOR SHRINKAGE AND EXPANSION OF THE PANELS.

- ROOF FRAMING NOTES:**
- METAL PLATE CONNECTED ROOF TRUSS FRAMING:**
- METAL PLATE CONNECTED WOOD TRUSSES SHALL BE SPACED @ 24" O.C UNLESS NOTED OTHERWISE. LOADING CRITERIA SHALL BE AS FOLLOWS:
    - TOP CHORD LIVE LOAD (TCLL): 20 PSF
    - REF MECHANICAL DRAWINGS FOR RTUS.
    - TOP CHORD DEAD LOAD (TCDL): 5 PSF - SINGLE-PLY MEMBRANE ROOF (NOT INCLUDING SELF-WEIGHT)
    - BOTTOM CHORD LIVE LOAD (BCLL): 10 PSF (NON-CONCURRENT WITH TCLL)
    - BOTTOM CHORD DEAD LOAD (BCDL): 5 PSF
    - TOP CHORD WIND LOAD. REF COMPONENTS AND CLADDING SCHEDULE
  - TRUSS DEFLECTION LIMITS: TRUSSES SHALL BE LIMITED TO THE FOLLOWING DEFLECTION LIMITS:
    - PITCHED ROOF TRUSSES: LIVE LOAD (L/240) TOTAL LOAD (L/180)
    - SHALLOW (< 4:12) PITCHED ROOF TRUSSES: LIVE LOAD (L/240) TOTAL LOAD (L/240)
    - PITCHED ROOF TRUSSES: 1.00 X DEFLECTION FROM ACTUAL DEAD LOAD.
  - DRAG TRUSSES SHALL BE PROVIDED DIRECTLY OVER INTERIOR SHEAR WALLS AND SHALL BE DESIGNED FOR A TOTAL FORCE EQUAL TO THE LENGTH OF THE SHEAR WALL MULTIPLIED BY THE ALLOWABLE SHEAR VALUE PROVIDED IN THE SHEAR WALL SCHEDULE FOR THAT SHEAR WALL TYPE.
  - TRUSS RESTRAINT/BRACING METHODS SHALL BE IN ACCORDANCE WITH BC31-B3 UNLESS NOTED OTHERWISE.

- ROOF DECKING NOTES:**
- ROOF DECKING SHALL BE 3/4" APA RATED SHEATHING (SPAN RATING 32/16).
  - PANELS SHALL SPAN 3 MORE RAFTERS IN THE .ONG DIMENSION.
  - PANEL CLIPS:
    - SINGLE-PLY OR MODIFIED BITUMEN ROOFING SYSTEMS:
      - LOW SLOPE ROOF (LESS THAN OR EQUAL TO 2:12)
        - DECKING SHALL HAVE PANEL EDGE CLIPS (H-CLIPS) LOCATED MIDWAY BETWEEN EACH SUPPORT.
        - SLOPE GREATER THAN 2:12
          - DECKING SHALL HAVE PANEL EDGE CLIPS (H-CLIPS) LOCATED MIDWAY BETWEEN EACH SUPPORT FOR ANY SPAN GREATER THAN 12.2' O.C.
      - ANY OTHER TYPE OF ROOFING SYSTEM
        - DECKING SHALL HAVE PANEL EDGE CLIPS (H-CLIPS) LOCATED MIDWAY BETWEEN EACH SUPPORT.

ROOF DECKING FASTENING		
ZONE	PANE EDGE / BOUNDARY	FIELD
ZONE 1	@ 4" O.C. MAX	@ 12" O.C. MAX
ZONE 2	@ 6" O.C. MAX	@ 6" O.C. MAX
ZONE 3	@ 4" O.C. MAX	@ 6" O.C. MAX
ZONE 3 OVERHANG	@ 3" O.C. MAX	@ 6" O.C. MAX

- ROOF DECKING FASTENING NOTES:**
- ALL NAILS SHALL BE 0.131" Ø X 2 1/2" RING SHANK NAILS
  - REFERENCE THE COMPONENTS AND CLADDING WIND PRESSURE MAP ON THE
  - GENERAL NOTES FOR ZONE LOCATIONS.
  - EDGE SPACING ALSO APPLIES OVER THE TOP OF SHEARWALLS.



6A  
S0.4 FLOOR PLAN - ROOF WIND ZONE  
1/16" = 1'-0"


BEAM SCHEDULE					
BEAM TAG	BEAM SIZE	STUD PACK - NUMBER OF STUDS	FACE-MOUNT HANGER	TOP-FLANGE HANGER	NOTE NUMBER
B226	(3)2X6	2	LUS26-2	HU26-2TF	1,2,3,4,6,7,8,9
B328	(3)2X8	2	LUS26-3	HU548TF	1,2,3,4,6,7,8,9
B3212	(3)2X12	3	HU210-3	HU212-3TF	1,2,3,4,6,7,8,9
B411	GL - 3 1/2" X 11 1/4"	3	HHU5410	HB3.56/11.25	3,4,5,6,7,8,9

- BEAM LEGEND NOTES:**
- MULTIPLE PLY DIMENSIONAL LUMBER BEAMS SHALL RECEIVE 1/2" PLYWOOD SHEATHING. SEE TYPICAL DETAIL.
  - FOR NAILING BUILT-UP BEAMS REFER TO DETAIL 2A/S4.0
  - FOR KING AND JACK STUD REQUIREMENTS FOR EXTERIOR HEADERS REFER TO DETAIL 4C/S4.1
  - FOR KING AND JACK STUD REQUIREMENTS IN INTERIOR HEADERS REFER TO DETAIL 5B/S4.1
  - BEAMS SHALL BE ANTHONY POWER BEAM GLUE LAMINATED BEAMS OR APPROVED EQUAL.
  - STUD PACKS ARE REQUIRED WHEN BEAM IS BEARING ON A WALL ASSEMBLY. STUD PACKS MUST CONTINUE ALL THE WAY TO THE FOUNDATION UNLESS TRANSFERRED BY A BEAM.
  - ALL STUDS IN STUD PACK MUST BE FASTENED PER MECHANICALLY LAMINATED BUILT-UP COLUMN-NAILED - REFER TO 6A/S4.1
  - SHEATHING AND/OR DRYWALL MUST BE ATTACHED TO EACH INDIVIDUAL STUD IN THE STUD PACK.
  - ALL STUDS IN STUD PACK MUST BE FASTENED PER MECHANICALLY LAMINATED BUILT-UP COLUMN-NAILED - REFER TO 6A/S4.1

WALL STUD SCHEDULE				
TOP OF WALL	MAX PLATE HT	EXTERIOR WALL	INTERIOR NON-LOAD BEARING	PARTY WALL
ROOF	8" - 11 5/8"	2X6 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 16" O.C.
3RD	10" - 8"	2X6 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 12" O.C.
2ND	10" - 9 5/8"	2X6 NO.2 @ 16" O.C.	2X4 STUD @ 16" O.C.	2X4 STUD @ 8" O.C.


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International--CC BY-SA 4.0)--freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International--CC BY-SA 4.0)--freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.




- NOTES:  
1. CUT AND/OR LAP THE VAPOR RETARDER AT THE BOTTOM OF EXTERIOR GRADE BEAMS. THE VAPOR RETARDER SHALL BE SECURED TO THE SIDES OF THE GRADE BEAM. IF LAPS ARE REQUIRED ON TOP OF THE SLAB, THEY MUST BE SEALED PER MFR RECOMMENDATIONS.  
2. ALL PIPE, DUCTING, BEAM, WIRE PENETRATIONS AND BLOCK OUTS SHOULD BE SEALED USING AFR RECOMMENDED WRAP, TAPE AND/OR MASTIC.  
3. IN THE EVENT THAT THE VAPOR RETARDER IS DAMAGED DURING OR AFTER INSTALLATION, REPAIRS MUST BE MADE. FOR HOLES, CUT A PIECE OF VAPOR RETARDER TO A SIZE AND SHAPE THAT COVERS ANY DAMAGE BY A MINIMUM OVERLAP OF 6" IN ALL DIRECTIONS. CLEAN ALL ADHESION AREAS OF DUST, OIL, MOISTURE, AND FROST. TAPE DOWN ALL EDGES USING AFR RECOMMENDED TAPE.


1B TYPICAL SUBGRADE AND VAPOR RETARDER PREPARATION  
NOT TO SCALE




2D TYPICAL INTERIOR GRADE BEAM  
NOT TO SCALE




1D TYPICAL REINFORCEMENT AT SLAB BLOCKOUT  
NOT TO SCALE




6C TYPICAL INTERIOR BEAM INTERSECTION  
NOT TO SCALE




5C TYPICAL SLAB-ON-GRADE SECTION  
NOT TO SCALE




4C TYPICAL REENRANT CORNER BARS  
NOT TO SCALE




3C TYPICAL SLAB DROP AT GRADE BEAM  
NOT TO SCALE




1C TYPICAL CORNER BARS  
NOT TO SCALE




B FLATWORK AT ENTRY DOOR




B FLATWORK NOT AT ENTRY DOOR




B AT PAVEMENT (DRIVE-IN)




6B TYPICAL FLATWORK/PAVEMENT DOWELS AT BUILDING  
NOT TO SCALE




4B TYPICAL VERTICAL PENETRATION IN GRADE BEAM  
NOT TO SCALE




4A TYPICAL HORIZONTAL PENETRATION IN BEAM  
NOT TO SCALE




2B TYPICAL UTILITY TRENCH UNDER BUILDING PAD BENTONITE PLUG AT EXTERIOR BEAM.  
NOT TO SCALE




1B VERTICAL PENETRATION THROUGH SLAB-ON-GRADE  
NOT TO SCALE



6A TYPICAL DROP TRANSITION IN GRADE BEAM - VERTICAL MOISTURE BARRIER  
NOT TO SCALE



2A TYPICAL DOUBLE WIDE INTERIOR GRADE BEAM  
NOT TO SCALE



1A TYPICAL CONDUITS EMBEDDED IN SLAB-ON-GRADE  
NOT TO SCALE

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

6 5 4 3 2 1

E

D

C

B

A

6

5

5

4

4

3


3

2


2

1


1




4C TYPICAL EXTERIOR GRADE BEAM - VERTICAL MOISTURE BARRIER  
NOT TO SCALE




5C TYPICAL GRADE BEAM AT STEEL STAIRS  
NOT TO SCALE




4C TYPICAL DROP TRANSITION IN GRADE BEAM TOP REINFORCEMENT AT SLAB LEAVE-OUT  
NOT TO SCALE




4B TYPICAL WIDENED FOOTING AT COLUMN - EMBEDDED BASE PLATE  
NOT TO SCALE




4C TYPICAL SPREAD FOOTING AT INTERIOR COLUMN  
NOT TO SCALE




2B TYPICAL SPREAD FOOTING AT INTERIOR COLUMN  
NOT TO SCALE




2C CSOG - TURN DOWN AT SLAB DROP  
NOT TO SCALE



1C TYPICAL TURN DOWN BEAM  
NOT TO SCALE




2B TYPICAL SPREAD FOOTING AT INTERIOR COLUMN  
NOT TO SCALE




6A TYPICAL MOMENT SIGN FOUNDATION  
NOT TO SCALE

COLUMN	BASE PLATE DIMENSIONS			CONDITION	ANCHOR BOLTS		
	X	W	T		NO./TYPE	DIA.	EMBEDMENT
HSS36X36	11"	13"	13"	INTERIOR	4/A	1"	1'-0"
HSS36X36	14"	16"	16"	INTERIOR	4/A	1"	1'-0"

5A TYPICAL BASEPLATE DETAIL  
NOT TO SCALE



3A TYPICAL ANCHOR ROD  
NOT TO SCALE



3A TYPICAL ANCHOR ROD  
NOT TO SCALE

ANCHOR ROD DIAMETER	HOLE DIAMETER	SQUARE PLATE WASHER SIZE	PLATE WASHER THICKNESS	TYPE B ANCHOR PLATE
5/8"	1.31/4"	1 1/2"	1/4"	PL17X10-4
3/4"	1.51/4"	2"	1/4"	PL17X10-4
7/8"	1.91/4"	2 1/2"	5/16"	PL17X10-4
1"	1.131/4"	3"	3/8"	PL11X10X10-5
1 1/2"	2.51/4"	3 1/2"	1/2"	PL11X10X10-5


- NOTES:
1. ALL TYPE A ANCHOR RODS SHALL BE F1554 GRADE 36.
  2. ALL TYPE B ANCHOR RODS SHALL BE F1554 GRADE 55.1.
  3. PLATE WASHERS MUST BE WELDED TO THE BASE PLATE WITH MINIMUM 3/16" FLLET WELD ALL AROUND.
  4. EMBEDMENT DEPTH ARE PRELIMINARY. FINAL EMBEDMENT TO BE PROVIDED AFTER REVIEW OF METAL BUILDING REACTIONS.
  5. ALL ANCHOR ROD HOLES SHALL ADHERE TO AISC DESIGN GUIDE 01, TABLE 2.3.
  6. THE DOUBLE NUT MAY BE OMITTED IF THE NUT IS TACK WELDED TO THE ROD.



This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)—freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


TYPICAL FASTENING SCHEDULE

CONNECTION ID	CONNECTION TYPE	FASTENING	FASTENING ORIENTATION
1	JOIST TO BIL OR GIRDER	(1) - 0.131" X 3"	TOENAIL
2	SOLE PLATE TO JOIST OR BLOCKING	0.148" X 3.1/2" NAILS @ 12" OC NAILS	FACE NAIL
3	TOP PLATE TO STUD	(3) - 0.131" X 3" NAILS	END NAIL
4	STUD TO SOLE PLATE - OPTION 1	(2) - 1/4" COMMON   (2) - 0.131" X 3" NAILS	END NAIL
5	STUD TO SOLE PLATE - OPTION 2	(4) 0.131" X 3" NAILS	TOENAIL
6	DOUBLE MULTIPLE STUDS	REFERENCE DETAIL 44/54.1	FACE NAIL
7	DOUBLE TOP PLATES	0.131" X 3" NAILS @ 12" OC	FACE NAIL
8	DOUBLE TOP PLATE SPICE	REFERENCE DETAIL 34/54.1	FACE NAIL
9	BLOCKING BETWEEN JOISTS/RAFTERS TO TOP PLATE	(3) - 0.131" X 3" NAILS	TOENAIL
10	BM JOIST TO TOP PLATE	0.131" X 3" NAILS @ 6" OC	TOENAIL
11	CEILING JOIST TO TOP PLATE	(3) - 0.131" X 3" NAILS	TOENAIL
12	CEILING JOIST LAP OVER PARTITION	(4) - 0.131" X 3" NAILS	FACE NAIL
13	CEILING JOIST TO PARALLEL RAFTERS	(4) - 0.131" X 3" NAILS	FACE NAIL
14	RAFTER TO TOP PLATE	(3) - 0.131" X 3" NAILS	TOENAIL
15	BUILT-UP CORNER STUDS	0.131" X 3" NAILS @ 14" OC	FACE NAIL
16	BUILT-UP BEAMS	REFERENCE DETAIL 24/54.0	FACE NAIL
17	COLLAR TIE TO RAFTER	(4) - 0.131" X 3" NAILS	FACE NAIL
18	JACK RAFTER TO HP	(4) - 0.131" X 3" NAILS	TOENAIL
19	RAFTER TO RIDGE BOARD/BEAM	(3) - 0.131" X 3" NAILS	TOENAIL
20	BLOCKING BT STUDS	(3) - 0.131" X 3" NAILS EACH SIDE	TOENAIL




NOTES:  
1. HOLE SIZE: THE HOLE DIAMETER SHALL NOT EXCEED 1/4" OR D/10, WHICHEVER IS SMALLER.  
2. SPACING: FOR LARGER HOLE DIAMETERS OR FOR HOLES OUTSIDE OF THE PERMITTED ZONES, WRITTEN PERMISSION MUST BE OBTAINED FROM THE EOR.  
3. LIMITATIONS: THE ABOVE CRITERIA ONLY APPLY TO SIMPLY SUPPORTED, UNIFORMLY LOADED GLUE LAMINATED BEAMS. FOR BEAMS THAT ARE EITHER CONTINUOUS ACROSS MULTIPLE SPANS OR THAT ARE SUPPORTING NON-UNIFORM LOADS, WRITTEN PERMISSION MUST BE OBTAINED FROM THE EOR.

4E ALLOWABLE HORIZONTAL HOLE LOCATIONS IN GLUE LAMINATED TIMBER BEAMS  
NOT TO SCALE




4D TYPICAL NAILING CONFIGURATIONS  
NOT TO SCALE


6D TYPICAL WOOD FASTENING SCHEDULE  
NOT TO SCALE



6C ALLOWABLE NOTCHING AND BORING OF FLOOR JOISTS  
NOT TO SCALE



4C ALLOWABLE SUBSTITUTION OF H2-5A CLIPS WITH FrameFAST SCREWS - UPLIFT LOAD PATH  
NOT TO SCALE



2C TYPICAL LVL MULTIPLE PLY FASTENING REQUIREMENTS  
NOT TO SCALE

FASTENER SCHEDULE - TO BEAM TOP FLANGE

L (ft)	PAF FASTENER	BOLT / ROD*
≤ 0.35	X-4.4 @ 12" OC	1/2" D @ 24" OC
0.35 < L ≤ 0.44	D5.47 @ 12" OC	1/2" D @ 24" OC
L > 0.44	N/A	1/2" D @ 12" OC

FASTENER SCHEDULE - TO BEAM WEB / BOTTOM FLANGE


L <sub>c</sub> (ft)	PAF FASTENER	BOLT / ROD*
≤ 0.35	(1) - X-4.4 @ 12" OC	(2) - 1/2" D @ 24" OC
0.35 < L <sub>c</sub> ≤ 0.44	(1) - D5.47 @ 12" OC	(2) - 1/2" D @ 24" OC
L <sub>c</sub> > 0.44	N/A	(2) - 1/2" D @ 12" OC

NAILER SCHEDULE - TO BEAM FLANGE


b (ft)	NAILER SIZE
≤ 5.5	2x4
5.5 < b ≤ 7.25	2x6
L > 7.25	2x8

NAILER SCHEDULE - TO BEAM WEB

d (ft)	NAILER SIZE
≤ 5	2x4
5 < d ≤ 6.75	2x6
6.75 < d ≤ 8.75	2x8
8.75 < d ≤ 10.75	2x10
10.75 < d ≤ 15	(2) - 2x8
15 < d ≤ 19	(2) - 2x10
19 < d ≤ 23	(2) - 2x12
d > 23	(3) - 2x8



6A WOOD NAILER TO TOP OF STRUCTURAL STEEL  
NOT TO SCALE




2A TYPICAL NAILING BUILT-UP BEAMS, GIRDERS & HEADERS  
NOT TO SCALE

RENOVATION Wranglers ENGINEERS  
Owner: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
Katherine@renotime.com | 979.450.9969

ARCHITECTURE  
Architect of Record: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076

DUDLEY  
Structural: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

amc ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Bumet, TX 78611  
info@amcengineers.com




OPENING WIDTH (FT)	REQUIRED NO. OF KING STUDS				NO. JACK STUDS	STRAP LAP LENGTH (IN)	
	8	9	10	12			
4.3	1	1	1	2	2	1	N/R
4	1	1	2	2	2	1	N/R
5	2	2	2	3	3	1	N/R
6	2	2	3	3	3	1	N/R
7	2	2	3	3	4	1	N/R
8	3	3	3	4	4	2	8
9	3	3	4	4	4	2	8
10	3	3	4	4	4	2	8

OPENING WIDTH (FT)	REQUIRED NO. OF KING STUDS				NO. JACK STUDS	STRAP LAP LENGTH (IN)	
	8	9	10	12			
4.3	1	1	1	1	1	1	N/R
4	1	1	1	1	1	1	N/R
5	1	1	1	1	2	1	N/R
6	1	1	1	2	2	1	N/R
7	1	1	2	2	2	1	N/R
8	1	1	2	2	2	2	8
9	1	2	2	2	2	2	8
10	1	2	2	2	3	2	8

- NOTES:  
1. MULTIPLE PILES MUST BE ATTACHED PER THE MECHANICALLY LAMINATED BUILT-UP COLUMN NAILED DETAIL.  
2. TABLE IS BASED ON A NOMINAL WIND PRESSURE OF 20 PSF AND GRAVITY LOADING OF 200 PLF.  
3. WALLS MUST BE CONNECTED TO THE FOUNDATION PER THE HEADERS.  
4. N/R = NOT REQUIRED. IF N/R, THEN REFERENCE NARROW OPENING DIAGRAM FOR CONNECTION REQUIREMENTS, OTHERWISE REFERENCE THE WIDE OPENING DIAGRAM.

4C TYPICAL EXTERIOR OPENING FRAMING  
NOT TO SCALE




OPENING WIDTH (FT)	REQUIRED NO. OF KING STUDS				NO. JACK STUDS	HEADER SIZE	
	8	9	10	12			
4.3	1	1	1	1	1	2x8H - 3x8H	
4	1	1	1	1	1	2x8H - 3x8H	
5	1	1	1	2	2	1	2x8H - 3x8H
6	1	1	2	2	2	1	2x8H - 3x8H
7	1	1	2	2	3	1	2x8H - 3x8H
8	2	2	2	3	3	2	2x10H - 3x10H
9	2	2	3	3	3	2	2x10H - 3x10H
10	2	2	3	3	3	2	2x10H - 3x10H


OPENING WIDTH (FT)	REQUIRED NO. OF KING STUDS				NO. JACK STUDS	HEADER SIZE	
	8	9	10	12			
4.3	1	1	1	1	1	2x8H - 3x8H	
4	1	1	1	1	1	2x8H - 3x8H	
5	1	1	1	2	2	1	2x8H - 3x8H
6	1	1	2	2	2	1	2x8H - 3x8H
7	1	1	2	2	3	1	2x8H - 3x8H
8	2	2	2	3	3	1	2x10H - 3x10H
9	2	2	3	3	3	1	2x10H - 3x10H
10	2	2	3	3	3	1	2x10H - 3x10H

- NOTES:  
1. LOAD BEARING WALLS AND ASSOCIATED HEADERS ARE INDICATED ON PLAN.


5B TYPICAL INTERIOR OPENING FRAMING  
NOT TO SCALE



2B ALLOWABLE STUD NOTCHING AND BORING IN INTERIOR NON-LOAD BEARING WALLS  
NOT TO SCALE




1B ALLOWABLE STUD NOTCHING AND BORING IN EXTERIOR & LOAD BEARING WALLS  
NOT TO SCALE




BUILT-UP SECTION	NAIL SIZE	SPACING	NO. ROWS	NOTES
[2] - 2x4	0.131 x 2"	6"	1	STAGGERED
[2] - 2x6	0.131 x 3"	8"	2	
[3] - 2x4	0.131 x 4"	6"	1	STAGGERED
[3] - 2x6	0.131 x 4"	8"	2	


6A MECHANICALLY LAMINATED BUILT-UP COLUMN (STUD PACK) - NAILED  
NOT TO SCALE




5A TYPICAL STRAP AT WIDE EXTERIOR OPENINGS  
NOT TO SCALE



4A TYPICAL CORNER AND INTERSECTION WALL STUDS (NOT AT SHEAR WALL)  
NOT TO SCALE



3A TYPICAL LOAD BEARING / SHEAR WALL DOUBLE TOP PLATE SPLICE  
NOT TO SCALE




2A TYPICAL BOTTOM PLATE ANCHORAGE  
NOT TO SCALE

TYPICAL WOOD FRAMING WALL DETAILS  
GREATEST PROJECT EVER - SOMEWHERE, TX


OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description




FLOOR-TO-FLOOR SCREW SCHEDULE	
12" < TRUSS DEPTH ≤ 14"	SIMPSON SDWF2720-TUM
14" < TRUSS DEPTH ≤ 18"	SIMPSON SDWF2724-TUM
18" < TRUSS DEPTH ≤ 24"	SIMPSON SDWF2730-TUM


**4D** TYPICAL FLOOR TRUSS PARALLEL TO EXTERIOR WALL - MULTI-STORY  
NOT TO SCALE




**2D** TYPICAL TRUSS STRONGBACK  
NOT TO SCALE




**3C** TYPICAL NON-LOAD BEARING WALL PARALLEL TO FLOOR TRUSSES  
NOT TO SCALE




**4C** TYPICAL NON-LOAD BEARING WALL ATTACHMENT TO PERPENDICULAR FLOOR TRUSS  
NOT TO SCALE




**2C** TYPICAL NON-LOAD BEARING WALL PARALLEL TO FLOOR TRUSS  
NOT TO SCALE




**1C** TYPICAL LOAD BEARING WALL PARALLEL TO FLOOR TRUSSES  
NOT TO SCALE




**1B** TYPICAL TRIMMABLE TRUSS STIFFENING AT INTERIOR SUPPORT  
NOT TO SCALE




**3B** TYPICAL LOAD BEARING WALL PERP. TO FLOOR TRUSS  
NOT TO SCALE




**2B** TYPICAL LOAD BEARING HEADER PARALLEL TO FLOOR TRUSSES  
NOT TO SCALE




**6A** TYPICAL SHEARWALL HOLDDOWN AT ELEVATED FLOOR  
NOT TO SCALE



**4A** TYPICAL SHEARWALL HOLDDOWN AT INTERIOR SHEAR WALL  
NOT TO SCALE



**3A** 061760 FLOOR - TRIMMABLE TRUSS BOTTOM CHORD BEARING ON EXTERIOR WALL  
NOT TO SCALE







**2A** TYPICAL INTERIOR BOTTOM CHORD BEARING AT PARTY WALL  
NOT TO SCALE

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International--CC BY-SA 4.0)--freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**openingdesign**  
Architect: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456

Date	Description

This project, like most OpeningDesign's projects, is open source. (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0) - freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.



Date	Description


This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)—freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.

**Renovation Wranglers**  
 Owner: Renovation Wranglers  
 102 E 26th St  
 Bryan, TX 77803  
 Katernca@wranglers.com | 979.450.9969


**LKB ARCHITECTURE**  
 Architect of Record: LKB Architecture  
 2929 Allen Pkwy Suite 200  
 Houston, TX 77019  
 isa@lkbarchitecture.com | 713.425.3076

**DUDLEY**  
 Structural: Dudley  
 6102 Imperial Loop Drive  
 College Station, TX 77845  
 (979) 777-0720


**AMC ENGINEERS**  
 MEP: AMC Engineers  
 508 E Jackson St # 552  
 Burnet, TX 78611  
 info@amcengineers.com




**6A** TYPICAL CRICKET FRAMING AT ROOF  
NOT TO SCALE



**5A** 0617.60 ROOF - BRACING AT INTERIOR SHEAR WALL  
NOT TO SCALE



SECTION A



**2A** ROOF - RAFTER ATTACHMENT INTO WALL  
NOT TO SCALE

TYPICAL WOOD ROOF TRUSS DETAILS  
GREATEST PROJECT EVER - SOMEWHERE, TX

Date	Description

S4.4

This project, like most OpeningDesign's projects, is open source (Attribution-ShareAlike 4.0 International-CC BY-SA 4.0)-freely available to any party for future use, assuming the terms such as Attribution and ShareAlike are honored.


**RENOVATION**  
Wranglers  
OWNER: Renovation Wranglers  
102 E 26th St  
Bryan, TX 77803  
kate@renovationwranglers.com | 979.450.9969

**LKB**  
ARCHITECTURE  
ARCHITECT OF RECORD: LKB Architecture  
2929 Allen Pkwy Suite 200  
Houston, TX 77019  
isa@lkbarchitecture.com | 713.425.3076


**DUDLEY**  
STRUCTURAL: Dudley  
6102 Imperial Loop Drive  
College Station, TX 77845  
(979) 777-0720

**amc**  
ENGINEERS  
MEP: AMC Engineers  
508 E Jackson St # 552  
Burnet, TX 78611  
info@amcengineers.com


**openingdesign**  
ARCHITECT: OpeningDesign  
17 S Fairchild | FL 7  
Madison, WI 53703  
ryan@openingdesign.com | 773.425.6456




**1C** CHANNEL TO HSS COLUMN CONNECTION - ALIGNED  
NOT TO SCALE




**3B** CHANNEL TO HSS COLUMN CONNECTION - ECCENTRIC  
NOT TO SCALE



**6B** TYPICAL CHANNEL CONNECTION AT BALCONY  
NOT TO SCALE



**3A** TYPICAL CHANNEL TO WALL STUD CONNECTION  
NOT TO SCALE



**6A** TYPICAL CHANNEL TO WALL STUD CONNECTIONX  
NOT TO SCALE